



QUARTERLY ENVIRONMENTAL MONITORING REPORT (QEMR) JUNE 2020

**DUNMORE RECYCLING & WASTE DEPOT
44 BUCKLEYS ROAD,
DUNMORE, NSW, 2529**

ENVIRONMENT PROTECTION LICENCE (EPL) 5984

Prepared For: **Shellharbour City Council**
Project Number: **ENRS0033**
Date: **July 2020**

ENRS

ENVIRONMENT & NATURAL RESOURCE SOLUTIONS
108 Jerry Bailey Road, Shoalhaven Heads, NSW
T 02 4448 5490 E: projects@enrs.com.au
ABN 68 600 154 596 WWW.ENRS.COM.AU

COMMERCIAL IN CONFIDENCE

This document has been prepared consistent with accepted scientific practice, supported by available data and resource conditions, as determined by limited data acquisition during the assessment period, evident at the site at the time. The designated recipients of this report accept all risks and responsibility for losses, damages, costs and other consequences resulting directly or indirectly from using the results of the interpretation, the data, and any information or conclusions drawn from it, whether or not caused by any negligent act or omission. To the maximum permitted by law, *ENRS Pty Ltd* excludes all liability to any person or identity, arising directly or indirectly from using the information or material contained herein.

INTELLECTUAL PROPERTY LAWS PROTECT THIS DOCUMENT



Copyright in the material provided in this document is owned by *ENRS Pty Ltd*, and third parties may only use the information in the ways described in this legal notice:

- Temporary copies may be generated, necessary to review the data.
- A single copy may be copied for research or personal use.
- The documents may not be changed, nor any part removed including copyright notice.
- Request in writing is required for any variation to the above.
- An acknowledgement to the source of any data published from this document is mandatory.

ACKNOWLEDGEMENTS

The project was conducted through close liaison with Shellharbour City Council (SCC) and ALS Environmental.

Author and Document Control

Written/Submitted by:	Reviewed / Approved by:
 Taite Beeston (BSc.) <i>Geologist & Environmental Consultant</i>	 Rohan Last (BSc. MSc) <i>Hydrogeologist & Environmental Scientist</i>

Record of Distribution

Copies	Report No. & Title	Status	Date	Prepared for:
1 x PDF	202006_ENRS0033r1e1_SCC Dunmore QEMR	Rev.1	14 th July 2020	ALS c/- Shellharbour City Council (SCC)

EXECUTIVE SUMMARY

Environment & Natural Resource Solutions (ENRS Pty Ltd) were commissioned as independent environmental consultants by *ALS Environmental* (Wollongong) on behalf of *Shellharbour City Council* (SCC) to prepare the Quarterly Monitoring Report for the Dunmore Recycling and Waste Depot (herein referred to as the Site).

This report summarises the results of field testing and laboratory analysis conducted by ALS for the June 2020 quarterly monitoring period. This Quarterly Report provides the necessary data assessment and analysis to meet requirements of the Site's Environment Protection Licence/s (EPL's); No.5984 and No.12903.

The Site was established in 1945 and has been managed by Shellharbour Council (SC) since 1983. The Site accepts putrescible and non-putrescible waste within its managed landfill cell. Recycling activities conducted at the site include Resource Recovery Centre, Revolve Centre and Food Organics and garden Organics (FOGO) processing.

Waste regulation in NSW is administered by the EPA under the Protection of the Environment Operations (POEO) Act (1997); the *Waste Avoidance and Resource Recovery Act* (2001).

The Site operates under the conditions of two (2) EPLs:

- **EPL No. 5984.** Landfill activities. Consisting of; extractive activities, waste disposal and composting.
- **EPL No. 12903.** Resource recovery activities. Consisting of; composting and waste storage within the FOGO Facilities and Resource Recovery Centre.

A copy of the relevant EPL sections outlining the sampling requirements are provided in **Appendix A** (EPL No. 5984). ENRS note that EPL No. 12903 does not specify sample points.

The objectives of this Quarterly Environmental Monitoring Report are to:

- Meet the environmental monitoring requirements of Sites EPLs; No. 5984 and 12903;
- Assess and analyse the environmental monitoring data for the Site against NSW EPA endorsed criteria;
- Identify any on-site or off-site impacts associated with operation of the Site;
- Advise SCC if the current environmental monitoring program is providing adequate information to identify potential environmental impacts from existing operations (if any) and provide recommendations on improvement to the monitoring program if required; and
- Document monitoring results in a Quarterly Environmental Monitoring Report.

The scope of work for this Quarterly Environmental Monitoring Report comprised the collation, assessment and reporting of Site data made available to ENRS from the quarterly December 2019 monitoring period in regard to the following tasks:

- Review previous reports and document the hydrogeological setting;
- Tabulate results of all monitoring data for both water and dust samples, collected and provided by ALS as required by the EPLs for the respective reporting period.
- Analysis and interpretation of all monitoring data (water, dust and landfill surface gas);

- Identification of any deficiencies in environmental performance identified by the monitoring data, trends or environmental incidents, and identification of remedial actions taken or proposed to be taken to address these deficiencies; and
- Recommendations on improving the environmental performance of the facility including improvement to the monitoring program.

Based on the findings obtained during the June 2020 quarterly monitoring program the following conclusions and recommendations are provided:

- Shallow groundwater flow is expected to mimic topography with low hydraulic gradients flowing towards the south and southeast towards Rocklow creek. The nearest sensitive receptors are likely to include; recreational users of the Minnamurra River estuary environs; down gradient stakeholders; and downgradient alluvial aquifers, swamps, Rocklow Creek, Minnamurra River and Groundwater Dependent Ecosystems near discharge zones;
- Groundwater reported exceedances of the assessment criteria for; ammonia, heavy metals, nitrate and salinity (EC) within multiple groundwater bores including; BH-1c, BH-3, BH-4, BH-9, BH-12r, BH-13, BH-14, BH-15, BH-19r. This is consistent with previous monitoring events;
- Onsite surface water samples (SWP-1, SW-2, SWP-4 and SWP-5) reported a single minor exceedance for pH above the ANZECC (2000) trigger values for 95% marine/freshwater. The remaining chemical leachate indicators were reported below the assessment criteria;
- Downgradient Rocklow Creek surface water samples (SWC-Up, SWC-2, SWC-down and SWC-down 2) were generally reported within the adopted Site Assessment Criteria. A single exceedance above the ANZECC (2000) guidelines for ammonium was reported in SWC-2. The result was the first exceedance within Rocklow creek for the 2020 monitoring period. Concentrations of key leachate indicators including ammonium and nitrate were below the ANZECC (2000) trigger values for marine waters in all other Rocklow Creek sample locations;
- The existing monitoring locations and sampling regime (specified in EPL 5984) is generally considered to provide a suitable assessment of surface water, leachate and groundwater conditions;
- Surface gas methane monitoring reported satisfactory results all within the adopted assessment criteria;
- Dust deposition gauges recorded satisfactory results below the guidelines provided in AS3580.10.1. Monitoring should continue in accordance with EPL 5984 requirements;
- No non-compliances with the EPL were reported during the June 2020 quarterly monitoring period;
- Based on this review of the quarterly June 2020 monitoring period, contaminants associated with the landfill cell, leachate dam/s and general site uses are considered to be relatively consistent with the range of historical results;

- Should any change in Site conditions or incident occur which causes a potential environmental impact, a suitable environmental professional should be engaged to further assess the Site and consider requirements for any additional monitoring; and
- This report must be read in conjunction with the attached Statement of Limitations.

TABLE OF CONTENTS

EXECUTIVE SUMMARY	II
1.0 INTRODUCTION	1
1.1 Project Background	1
1.1.1 Site History.....	1
1.1.2 EPL Requirements	1
1.2 Objectives	1
1.3 Scope of Work	2
2.0 SITE DESCRIPTION	2
2.1 Location	2
2.2 Surrounding Landuse	3
2.2.1 Sensitive Receptors	4
2.3 Topography & Drainage.....	4
2.4 Soil Landscape	4
2.5 Geology	4
2.6 Hydrogeology.....	4
2.6.1 Existing Bores	5
2.6.2 Flow Regime	5
2.7 Surface Water.....	5
3.0 ASSESSMENT CRITERIA	5
3.1 Contaminants of Potential Concern	5
3.2 Water Quality Guidelines	6
3.2.1 ANZECC Guidelines	6
3.2.2 National Environmental Protection Measure (NEPM)	6
3.3 Dust Deposition Assessment Criteria	7
3.4 Surface Methane GAS Assessment Criteria	7
4.0 SAMPLING METHODOLOGY	7
4.1 Water Sampling	8
4.1.1 Location of Water Monitoring Points.....	8
4.1.2 Depth to Water.....	8
4.1.3 Sample Collection	8
4.1.4 Groundwater Sampling.....	8
4.1.5 Field Testing	9
4.2 Dust Deposition sampling	9
4.3 Surface Methane Gas Monitoring	9
4.4 Laboratory Analysis	10
5.0 QUALITY ASSURANCE AND QUALITY CONTROL (QA/QC)	10

5.1	Data Quality Objectives	10
5.2	QA/QC Procedures	10
5.3	EPL Non-Compliance	11
6.0	WATER QUALITY RESULTS	11
6.1	Overflow Results.....	11
6.2	Field Testing	11
6.3	Physical Indicators	11
6.3.1	Salinity (EC & TDS).....	11
6.3.2	Dissolved Oxygen	12
6.3.3	pH	12
6.3.4	Total Suspended Solids (TSS)	13
6.4	Inorganic Analytes	13
6.4.1	Nutrients.....	13
6.4.2	Metals & Metalloids	13
6.5	Organic Analytes	14
6.5.1	Total Organic Carbon	14
6.6	Summary of Water Quality Exceedances	15
7.0	DUST GAUGE RESULTS	15
8.0	SURFACE METHANE GAS RESULTS.....	16
9.0	ENVIRONMENTAL ASSESSMENT	16
9.1	Monitoring Point Summary.....	16
10.0	CONCLUSION AND RECOMMENDATIONS	16
11.0	LIMITATIONS.....	18
12.0	REFERENCES	19

LIST OF TABLES, FIGURES & APPENDICES

TABLES

- Table 1: Site Identification
- Table 2: Surrounding Land use
- Table 3: Groundwater Assessment Criteria
- Table 4: Adopted Guideline Criteria
- Table 5: Data Quality Objectives
- Table 6: Summary of Quarterly Water Monitoring Exceedances
- Table 7: Summary of Dust Gauge Results
- Table 8: Water Quality Results

FIGURES

- Figure 1: Site Location Map
- Figure 2: Sampling Points & Site Plan
- Figure 3: Surface Methane Gas Sample Transects
- Figure 4: Regional Geology
- Figure 5: Registered Bores

APPENDICES

- Appendix A EPL 5984 Sampling Point Summary (NSW EPA, 04/03/2020)
- Appendix B Laboratory Chain of Custody (COC) & Certificates of Analysis (COA) – Water Samples
- Appendix C Laboratory Chain of Custody (COC) & Certificates of Analysis (COA) – Dust Samples
- Appendix D Surface Gas (Methane) Field Sheets
- Appendix E Calibration Certificates

1.0 INTRODUCTION

Environment & Natural Resource Solutions (ENRS Pty Ltd) were commissioned as independent environmental consultants by *ALS Environmental* (Wollongong) on behalf of *Shellharbour City Council* (SCC) to prepare the Quarterly Monitoring Report for the Dunmore Recycling and Waste Depot (herein referred to as the Site).

This report summarises the results of field testing and laboratory analysis conducted by ALS for the June 2020 quarterly monitoring period. This Quarterly Report provides the necessary data assessment and analysis to meet requirements of the Site's Environment Protection Licence/s (EPL's); No.5984 and No.12903.

1.1 PROJECT BACKGROUND

1.1.1 Site History

The Site was established in 1945 and has been managed by Shellharbour Council (SC) since 1983. The Site accepts putrescible and non-putrescible waste within its managed landfill cell. Recycling activities conducted at the site include Resource Recovery Centre, Revolve Centre and Food Organics and garden Organics (FOGO) processing.

1.1.2 EPL Requirements

Waste regulation in NSW is administered by the EPA under the Protection of the Environment Operations (POEO) Act (1997); the *Waste Avoidance and Resource Recovery Act* (2001).

The Site operates under the conditions of two (2) EPLs:

- **EPL No. 5984.** Landfill activities. Consisting of; extractive activities, waste disposal and composting.
- **EPL No. 12903.** Resource recovery activities. Consisting of; composting and waste storage within the FOGO Facilities and Resource Recovery Centre.

A copy of the relevant EPL sections outlining the sampling requirements are provided in **Appendix A** (EPL No. 5984). ENRS note that EPL No. 12903 does not specify sample points.

1.2 OBJECTIVES

The objectives of this Quarterly Environmental Monitoring Report are to:

- Meet the environmental monitoring requirements of Sites EPLs; No. 5984 and 12903;
- Assess and analyse the environmental monitoring data for the Site against NSW EPA endorsed criteria;
- Identify any on-site or off-site impacts associated with operation of the Site;

- Advise SCC if the current environmental monitoring program is providing adequate information to identify potential environmental impacts from existing operations (if any) and provide recommendations on improvement to the monitoring program if required; and
- Document monitoring results in a Quarterly Environmental Monitoring Report.

1.3 SCOPE OF WORK

The scope of work for this Quarterly Environmental Monitoring Report comprised the collation, assessment and reporting of Site data made available to ENRS from the quarterly December 2019 monitoring period in regard to the following tasks:

- Review previous reports and document the hydrogeological setting;
- Tabulate results of all monitoring data for both water and dust samples, collected and provided by ALS as required by the EPLs for the respective reporting period.
- Analysis and interpretation of all monitoring data (water, dust and landfill surface gas);
- Identification of any deficiencies in environmental performance identified by the monitoring data, trends or environmental incidents, and identification of remedial actions taken or proposed to be taken to address these deficiencies; and
- Recommendations on improving the environmental performance of the facility including improvement to the monitoring program.

2.0 SITE DESCRIPTION

2.1 LOCATION


The Site is located at 44 Buckleys Road, Dunmore, NSW, 2529, legally defined as Lot 21 in Deposited Plan 653009 and Lot 1 Deposited Plan 419907. The Site is situated approximately three and a half (3.5) kilometres southwest of the Shellharbour town centre. The area's regional location is defined in **Figure 1** below. Details of the Site boundary and sampling points are provided in the Site Plan (see **Figure 2**). The key features required to identify the Site are summarised in **Table 1**.

Table 1: Site Identification

Aspect	Description
Site	Dunmore Recycling and Waste Depot
Street Address	44 Buckleys Road, Dunmore, NSW 2529
Site Area	72.36 hectares
Title Identifier	Lot 21 DP 653009, Lot 1 DP 419907

Aspect	Description
Zoning	RU1 Primary Production
Local Government Area	Shellharbour City Council

Figure 1: Site Location Map



Source: SIX Maps (<https://maps.six.nsw.gov.au/>) (cited 16/01/2020)

2.2 SURROUNDING LANDUSE

The current activities and operations on adjacent properties and the surrounding area include:

Table 2: Surrounding Land use

Direction	Land Use
North:	Buckleys Road, commercial infrastructure and open grassland. Residential dwellings along the northwest border of the Site. Golf course further to the northeast.
East:	Dunmore Resources and Recycling facility immediately to the east, bushland to the southeast.
South:	Bushland, Rocklow Creek (300m from landfill activities). Further to Kiama Community Recycling Centre and Riverside Drive.
West:	Bushland to the southwest, scattered trees immediately to the west and further to the Princes Highway. Boral Quarries complex beyond the Highway. Residential dwellings to the Northwest.

2.2.1 Sensitive Receptors

The nearest sensitive receptors are likely to include:

- Recreational users of the Minnamurra River estuary environs;
- Down gradient stakeholders; and
- Down gradient alluvial aquifers, swamps, Rocklow Creek, Minnamurra River and Groundwater Dependent Ecosystems (GDE) near discharge zones.

2.3 TOPOGRAPHY & DRAINAGE

A review of the current series Albion Park (90281N) 1:25,000 topographic map sheet was conducted to assess the regional topography and to identify potential runoff and groundwater controls in the region. Topography provides a useful indicator for groundwater controls including gradient and flow path.

The Site presents low topographic relief, remaining between approximately 3-5 mAHD across the entirety of the Site. The regional topographic gradient trends south-southeast towards Rocklow Creek and Minnamurra River.

2.4 SOIL LANDSCAPE

The previous annual monitoring report (Environmental Earth Sciences 2018) reported the soil profile at the Site as organic, black, massive sandy loam topsoil overlying loose bleached light grey sand with iron staining in the subsoil.

Review of the online *Shellharbour City Council Acid Sulphate Soil Risk Map* indicates that the Site lies within a **Class 3** area, suggesting that works beyond 1 metre below the ground level (mbGL) have the potential to encounter Acid Sulphate Soils (ASS).

2.5 GEOLOGY

A review of the Site geology was undertaken with reference to the Wollongong 1:250,000 geological series sheet (Si56.9) and the Shellharbour-Kiama area coastal quaternary 1:50,000 geology sheet. The Site is predominately underlain by the Quaternary alluvial deposits (Qal) characterised as Holocene backbarrier flat; marine sand, silt, clay, gravel and shell (Qhbf). The northern most corner of the site is intersected by the Gerringong Volcanics (Pbb) characterised by Latite. Based on the mapped geology, previous investigations and borehole logs, the Site infrastructure including the landfill cell is located within the alluvial deposits.

2.6 HYDROGEOLOGY

Groundwater resources in the area are expected to be associated with *Shallow unconfined* alluvial and unconsolidated systems, generally less than 20 m in depth with moderate to high transmissivity, variable water quality, and strongly controlled by rainfall recharge.

2.6.1 Existing Bores

A network of groundwater monitoring bores is installed at the Site to provide specific data on the quality and nature of groundwater.

A review of the *NSW Office of Water (NOW)* existing bore records was conducted to develop the conceptual understanding of regional groundwater conditions, including aquifer depths, yields, water quality, and distribution. A search of the Bureau of Meteorology Australian Groundwater Explorer groundwater database identified a total of eighty-eight (88) registered bores within one and a half (1.5) kilometres of the Site (see **Figure 5**). Registered bores in the area are predominantly associated with the Landfill Site and with the quarry complex (*Boral Site*) to the west of the EPL Site. The majority of bores are registered for monitoring purposes, excluding a single well (GW044447), which is registered for stock and domestic purposes. The stock bore is located approximately one (1) kilometre to the north of the Site, on the western side of the Princes Highway, which is considered to be up gradient of the Site and not in direct hydraulic connectivity. Registered bore depths are between 1.25 m and 22 m. Bore records indicate shallow unconsolidated aquifer systems.

2.6.2 Flow Regime

Previous reports (Environmental Earth Sciences 2018) have identified that groundwater flows vary across the Site, but the general trend is south, towards Rocklow Creek.

Based on the unconfined nature of the aquifer, the shallow groundwater flow is inferred to mimic topography with low to moderate hydraulic gradients flowing towards the south.

The Site and adjoining land, is largely unsealed with potential for local recharge from rainfall infiltration. Likely discharge areas are predominantly to the south and east of the Site including swamps and Rocklow Creek. The waterbodies surrounding the Site are recognised as State Environmental Planning Policy No.14 (SEPP14) registered wetlands and Proximity Areas for Coastal Wetlands border the eastern, southern and western boundaries of the Site.

2.7 SURFACE WATER

The Site topography indicates that surface water flow will generally trend to the east towards off Site wetlands and southeast towards Rocklow Creek. These present the primary regional drainage structures for natural surface water and runoff. A series of stormwater infrastructure is present at the Site which is expected to capture run off. Infrastructure includes but not limited to; stormwater drains; sedimentation ponds; levee banks; collection and diversion drains; and leachate dams.

3.0 ASSESSMENT CRITERIA

3.1 CONTAMINANTS OF POTENTIAL CONCERN

This section of the report provides a summary of the Contaminants of Potential Concern (CoPC) associated with the Site. CoPC's are identified in the Sites EPL/s which document the

CoPC and water quality indicators required to be monitored. Analytical requirements for all water sampling are provided in Appendix A.

3.2 WATER QUALITY GUIDELINES

Nationally developed guidelines are provided in the National Water Quality Management Strategy (NWQMS): Guidelines for Groundwater Protection in Australia (ARMCANZ & ANZECC 1995). For the purpose of this assessment, the relevant criteria selected to protect environmental values are summarised in **Table 3** below:

Table 3: Groundwater Assessment Criteria

Environmental Value	Relevant Guideline
Ecosystems / Health Screening Levels	ANZG (2018) (Australian and New Zealand Guidelines for Fresh and Marine Water Quality).
	National Environment Protection Measure (NEPM) (2013).
Drinking Water	Australian Drinking Water Guidelines (ADWG) (2018)

3.2.1 ANZECC Guidelines

The relevant criteria for this water quality assessment are the Australian and New Zealand Guidelines for Fresh and Marine Water Quality (ANZG;2018). The ANZG (2018) provide Default Guideline Values (DGVs) for four (4) levels of protection categorised by the percentage of species possibly affected, being 80%, 90%, 95% or 99% of species. Values for a level of protection for 95% of species in a marine environment have been adopted and are displayed in **Table 4**. Where DVGs are not available reference is made against the ANZECC (2000) Trigger Values (TVs). The *NSW Office of Water* (DECCW;2007) endorsed groundwater management guidelines recommend assessment for aquatic ecosystems based on the **95 per cent of species level of protection**.

Table 4: Adopted Guideline Criteria

Parameter	Groundwater Guideline	Surface water Guideline
Ammonia	0.91 mg/L	1.88 mg/L
Nitrate	10.6 mg/L	10.6 mg/L
pH	6.5-8.0 pH units	6.5-8.0 pH units
Soluble Iron	0.3 mg/L	0.3 mg/L
Manganese	1.9 mg/L	1.9 mg/L
Electrical Conductivity	125-2200 µS/cm	-

3.2.2 National Environmental Protection Measure (NEPM)

The NSW EPA has endorsed the use of the Groundwater Investigation Levels (GILs) given in the 2013 ASC NEPM ‘Schedule B(1) Guideline on the Investigation Levels for Soil and

Groundwater’. The latest NEPM provide a framework for risk-based assessment of groundwater contamination.

Groundwater Health Screening Levels (HSLs) are provided for four (4) land use categories for vapour intrusion (Table 1A[4]) associated with Total Recoverable Hydrocarbons TRH (F1 & F2) and BTEX compounds.

NEPM	Description of Land use Categories
HIL A	Residential A with garden/accessible soil also includes children’s day care centres, preschools and primary schools.
HIL B	Residential B with minimal opportunities for soil access; includes buildings with fully and permanently paved yard space such as high-rise buildings and apartments.
HIL C	Recreational C includes public open space such as parks, playgrounds, playing fields (e.g. ovals), secondary schools and unpaved footpaths.
HIL D	Commercial/industrial D includes premises such as shops, offices, factories and industrial sites.
GILs	Groundwater Investigation Levels (GILs) should be applied based on the receiving environment and groundwater resources. GILs are provided in NEPM Table 1C for; Fresh Waters; Marine Waters; and Drinking Water;
EILs	Ecological Investigation Levels (EILs) for common contaminants in the top two (2) metres of soil based on three (3) generic land use settings: <ul style="list-style-type: none"> • Areas of ecological significance; • Urban residential areas and public open space; and Commercial and industrial land uses.

3.3 DUST DEPOSITION ASSESSMENT CRITERIA

Criteria for collection and assessment of dust deposition concentrations are provided within the Australian standard AS3580.10.1 - Methods for sampling and analysis of ambient air; method 10.1- Determination of particulate matter - Deposited matter - Gravimetric method. AS3580.10.1 provides an acceptable level of 4 g/m²/month.

3.4 SURFACE METHANE GAS ASSESSMENT CRITERIA

The NSW EPA Solid Waste Landfill Guidelines 2nd Edition (2016) provides sampling methodologies and threshold for surface methane gas concentrations at landfill sites. The acceptable threshold for capped landfills is 500 parts per million (ppm) at 5 cm above the capping surface.

4.0 SAMPLING METHODOLOGY

Field sampling was conducted by *ALS Environmental* (Wollongong) as commissioned by SCC in June 2020. ENRS understands that sampling was conducted in accordance with ALS sampling protocols with reference to current industry standards and Code of Practices. The following sub-sections provide a summary of the sampling methodologies.

Monitoring frequency is defined by the EPL/s and is designed to capture necessary site data to support assessment of Site conditions (quarterly and annual), any long-term trends or overflow events. Monitoring is conducted quarterly and annually for selected analytes with additional overflow and event-based sampling triggered by Site conditions.

4.1 WATER SAMPLING

4.1.1 Location of Water Monitoring Points

Groundwater and surface water monitoring requirements are defined by the EPL No. 5984, as provided in Appendix A. In summary the sampling regime collected samples from; eight (8) surface waters; nine (9) groundwater monitoring wells; and two (2) leachate points. Sampling locations are illustrated in **Figure 2** attached.

4.1.2 Depth to Water

Prior to sampling, the depth to the groundwater table was measured from the top of casing (TOC) using a water dipper and clear disposable bailer. The bores were inspected for the presence of hydrocarbon and the thickness of any LNAPL was measured visually in clear disposable bailers. **No LNAPL was identified in monitoring Wells.**

4.1.3 Sample Collection

Sampling is conducted independently by *ALS Environmental* under contract with *SCC*. Chain of Custody records and field sheets are provided in Appendix D. ENRS understand sampling is conducted in accordance with *ALS* sampling protocols.

4.1.4 Groundwater Sampling

Groundwater Wells were sampled in order of distance from any areas of known contamination to ensure that lower contaminated Wells are sampled before likely higher contaminated Wells. Groundwater bores were purged prior to sampling by removing at least three (3) well volumes or low flow parameter stabilisation methods applied with field sheets provided to document pumping volumes and field parameters. Samples were collected using clear disposal bailers. and were sealed in laboratory-prepared sampling containers appropriate for the analysis. All samples were stored on ice immediately after their collection and transported to the laboratory under Chain of Custody (CoC) documentation.

Surface water and leachate samples were collected using as 'grab samples' from the midpoint of the structure and at mid-depth.

Any loss of volatile compounds was kept to a minimum by employing the following sampling techniques:

- Minimal practical disturbance during sampling;
- Samples placed in sample containers as soon as possible;
- Sample containers contain zero headspace;

- Samples placed directly on ice and transported to the laboratory as soon as possible; and
- Employing the most appropriate analytical method to minimise volatile losses at the laboratory.

4.1.5 Field Testing

Field testing was conducted during bore purging and sampling to record physical water parameters. A multi-probe water quality meter was used to measure the following parameters:

- Oxygen Reduction Potential (ORP, representing redox).
- Electrical Conductivity (Salinity - EC);
- Temperature; and
- pH (Acidity).

4.2 DUST DEPOSITION SAMPLING

Measurement of Dust deposition was carried out in accordance with the Australian Standard AS3580.10.1 (2016). This Australian Standard provides a mean of determining the mean surface concentration of deposited matter from the atmosphere.

Dust collection gauges were set up for a one (1) month period between the **15th May** and **17th June 2020**. A total of four (4) dust monitoring locations were considered adequate to assess site conditions. ENRS note that the June 2020 quarterly sampling was the third event to four (4) dust gauges.

4.3 SURFACE METHANE GAS MONITORING

The concentration of methane gas (in units of ppm) at the Site was carried out in accordance with EPA Guidelines Solid Waste Landfill 2nd Edition 2016. On the day of sampling the wind speed was below 10 km/hr. Testing was conducted using a calibrated *LaserOne* portable gas monitor specifically designed for landfill gas monitoring. A calibration Certificate is provided in Appendix E.

One field technician commenced data collection along transect lines in a grid pattern across the landfill surface at 25-metre spacings. A site plan depicting the sampled transect line is provide in **Figure 3**. Transects were recorded using a Magellan *SporTrak* GPS. The concentration of methane gas was measured at a height of 5 cm above the ground in areas with intermediate or final cover over the emplaced waste. The concentration of methane gas was also recorded in any buildings located within a distance of 250 m of the deposited waste, and any depressions or surface fissures away from the sampling grid were also investigated.

4.4 LABORATORY ANALYSIS

ALS, a NATA accredited laboratory, was contracted by SC to undertake the sample analysis in accordance with current standards. Laboratory QA/QC results are detailed in the Laboratory reports contained in the appendices section of this report.

5.0 QUALITY ASSURANCE AND QUALITY CONTROL (QA/QC)

5.1 DATA QUALITY OBJECTIVES

Data Quality Objectives (DQO) are required to define the quality and quantity of data needed to support management decisions. The process for establishing DQO's is documented by Australian Standard: AS 4482.1-2005 and referenced by the National Environment Protection (Assessment of Site Contamination) Measure (NEPC;2013). The DQO's for the investigation were to obtain representative data to allow assessment of:

- groundwater quality;
- The risks posed to human health and the environment, including potential future users of the Site; and
- The requirements for any further investigative works.

The assessment was conducted to a standard consistent with generally accepted and current professional consulting practice for such an investigation. The evaluation criteria adopted for the investigation are summarised in **Table 5**.

Table 5: Data Quality Objectives

DQO	Evaluation Criteria
Documentation completeness	Completion of field records, chain of custody documentation, laboratory test certificates from NATA-accredited laboratories.
Data comparability	Use of appropriate techniques for the sampling, storage and transportation of samples. Use of NATA accredited laboratory using NEPM endorsed procedures.
Data representativeness	Adequate sampling coverage of all areas of environmental concern at the Site, and selection of representative samples.
Precision and accuracy for sampling and analysis	Use properly trained and qualified field personnel and achieve field and laboratory QA/ QC criteria.

5.2 QA/QC PROCEDURES

Data provided for the purpose of this report by SC was prepared by ALS. ALS is NATA accredited for the laboratory testing. The QA/QC indicators as provided to ENRS either all

complied with the required standards, or showed variations that would have no significant effect on the quality of the data or the conclusions of this environmental assessment. Therefore, the data is considered acceptable for use in this assessment.

It should be noted that whilst the EPL does not require field duplicates, ENRS recommend sampling include rinsate samples and field duplicates at the standard rate of 1 in 10, or field QA/QC is conducted in accordance with ALS procedures.

5.3 EPL NON-COMPLIANCE

Monitoring requirements are defined by the EPL. ENRS understand the June 2020 quarterly monitoring results identified no non-compliance with the terms of the EPL.

6.0 WATER QUALITY RESULTS

Laboratory results for groundwater and surface water were provided to ENRS for tabulation and comparison with relevant EPL assessment criteria. A summary of results is provided in **Table 8** with comparison against the relevant Site Assessment Criteria (SAC). Exceedances of relevant guidelines are also summarised in **Table 6**. The laboratory certificates of analysis are provided in Appendix B.

6.1 OVERFLOW RESULTS

ENRS understand no overflow events were recorded during the June 2020 quarterly monitoring period. Hence, no water samples were collected by ALS and no results are presented for this reporting period.

6.2 FIELD TESTING

Field testing is conducted by ALS during sampling to record physical water parameters. A water quality meter is used to measure the following parameters in the field:

- Electrical Conductivity (Salinity);
- pH (Acidity); and
- Dissolved Oxygen

6.3 PHYSICAL INDICATORS

6.3.1 Salinity (EC & TDS)

Salinity is reported by the laboratory as either Electrical Conductivity (EC) or Total Dissolved Solids (TDS). The ANZECC guidelines document a conversion ratio for of $0.68 \text{ mg/L} = 0.68 \text{ EC } (\mu\text{S/cm})$. Table 3.3.3 of the ANZECC (2000) guidelines document default TV for EC in lowland freshwater rivers between $125 \mu\text{S/cm} - 2,200 \mu\text{S/cm}$ (~1,500 mg/L).

Groundwater

Salinity in groundwater is typically higher than surface water due to mineral dissolution. Groundwater salinity at the Site was generally reported above the freshwater SAC of 2,200 $\mu\text{S/cm}$. Elevated results were reported in six (6) groundwater bores ranging between; **2,350 $\mu\text{S/cm}$ (BH-14)** and **6,740 $\mu\text{S/cm}$ (BH-1)**. Results are consistent with the previous 2020 quarterly monitoring events.

Leachate

Leachate salinity for the quarterly June 2020 monitoring period was reported to be **11,000 $\mu\text{S/cm}$ (LP1)** and **12,000 $\mu\text{S/cm}$ (Sump)** which is above the TV.

6.3.2 Dissolved Oxygen

Levels of Dissolved Oxygen (DO) were measured in the field during sampling. DO reflects the equilibrium between oxygen-consuming processes and oxygen-releasing processes. DO can initiate redox reactions resulting in the uptake or release of nutrients. Low DO concentrations can result in adverse effects on many aquatic organisms which depend on oxygen for their efficient metabolism. At reduced DO concentrations many compounds become increasingly toxic, for example Zinc, Lead, Copper, phenols, cyanide, hydrogen sulfide and Ammonia.

The ANZECC (2000) guidelines Table 3.3.2 outlines a range between 85% to 110% saturation for low land rivers. Assuming a water temperature of 18°C this is equivalent to approximately 7-11 mg/L or ppm.

Dissolved Oxygen was recorded for Leachate only, at **0.35 mg/L (Sump)** and **7.0 mg/L (LP1)**.

6.3.3 pH

pH is a measure of hydrogen activity. pH determines the balance between positive hydrogen ions (H^+) and negative hydroxyl ions (OH^-) and provides a test of water acidity (low pH) or alkalinity (high pH). Most natural freshwaters have a pH in the range 6.5 to 8.0. Changes in pH may affect the physiological functioning of biota and affect the toxicity of contaminants. Both increases and decreases in pH can result in adverse effects, although decreases are likely to cause more significant problems. Low pH indicates acidic conditions which may increase the mobility of heavy metals, whilst high pH indicates alkaline conditions which may also generate Ammonia. Previous investigations of other regional Landfill Sites in the Illawarra-Shoalhaven (Forbes Rigby;1996) report regionally acidic groundwater with low readings in the range of 4.3 pH associated with silica saturation and oxidation of accessory marcasites grains (iron sulphide).

Surface Water

Surface water reported pH values of between **pH 7.0 (SWP-up)** and **pH 8.1 (SWP-4)**.

Groundwater

Groundwater pH was reported between **pH 6.6 (BH-14)** and **pH 7.5 (BH-3)**. All groundwater results were reported within the ANZECC recommended range of pH 6.5-8.0. The results are largely within the historical range of values.

6.3.4 Total Suspended Solids (TSS)

TSS provides a measure of turbidity reported as the mass of fine inorganic particles suspended in the water. Measurement of TSS provides a valuable indication of the sediment and potential nutrient load. Elevated TSS decreases light penetration whilst phosphorus is absorbed onto sediment surfaces.

TSS was reported for surface water only. Concentrations were reported between **6 mg/L** (SWC-down) and **20 mg/L** (SWP-1).

6.4 INORGANIC ANALYTES

6.4.1 Nutrients

Water samples were analysed for select nutrients including Ammonia, Ammonium, Nitrate and Nitrite. The most bio-available forms of Nitrogen are Ammonium (NH₄⁺) and Nitrate (NO₃⁻). Ammonia is an oxygen-consuming compound and is toxic to aquatic biota at elevated concentrations. Ammonia toxicity increases under low oxygen levels and higher pH.

Ammonia

Ammonia was measured within groundwater monitoring bores between **0.42 mg/L** (BH-14) and **131 mg/L** (BH-1c). Eight (8) out of the nine (9) groundwater wells reported exceedances over the adopted trigger value of 0.91 mg/L. This is consistent with historical values.

Ammonia in leachate was reported at **60 mg/L** (LP1) and **110 mg/L** (Sump). High ammonia concentrations are expected in untreated leachate.

Ammonium

Ammonium was measured at Rocklow Creek surface water monitoring locations between **0.28 mg/L** (SWC-down 2) and **1.68 mg/L** (SWC-2). The SWC-2 result exceeds the adopted trigger value of 0.91 mg/L.

Nitrate

Results for Nitrate in groundwater were reported between **<.01 mg/L** in multiple bores and **61.4 mg/L** (BH-14). A total of four (4) exceedances in groundwater were reported above the TV of 0.7mg/L including: **61.4 mg/L** (BH-14), **16.9 mg/L** (BH-3), **1.76 mg/L** (BH-12r) and **0.97 mg/L** (BH-13).

Nitrate in Rocklow Creek surface water samples were all reported below the TV of 0.7mg/L. The results are considered satisfactory.

Nitrate in leachate was reported below the laboratory lower limit of detection of <0.2mg/L.

6.4.2 Metals & Metalloids

Magnesium (Total Mg)

Magnesium was analysed in selected surface water samples. Concentrations of magnesium in surface water were reported between **12 mg/L** (SWP-1) and **1,060 mg/L** (SWC-down).

Manganese (Total Mn)

Manganese was analysed in groundwater and leachate sampling points. Concentrations of Manganese in groundwater were reported between **0.122 mg/L** (BH-1c) and **1 mg/L** (BH-9). Leachate concentrations were reported as **0.605 mg/L** (LP1) and **0.672 mg/L** (Sump). These values are below the adopted TV (1.9 mg/L 95% of Species - freshwater) and are considered acceptable. Concentrations of Manganese should continue to be reviewed during subsequent monitoring events.

6.5 ORGANIC ANALYTES

6.5.1 Total Organic Carbon

Total Organic Carbon (TOC) provides a measure of the total concentration of organic material in a water sample. TOC is typically higher in surface water than groundwater, however high TOC is also characteristic of leachate from landfill. TOC provides a marker for biological activity associated with contaminant degradation and can be used to delineate contaminant plumes. TOC influences geochemical processes by:

- acting as proton donors/acceptors;
- providing pH buffering;
- participating in mineral dissolution/precipitation reactions; and
- providing carbon substrate for microbe-based biodegradation.

TOC was reported during monitoring period at the following concentrations:

- Groundwater; between **15 mg/L** (BH-3 & BH-12r) and **179 mg/L** (BH-1c); and
- Leachate; **238 mg/L** (Sump) and **309 mg/L** (LP1).

6.6 SUMMARY OF WATER QUALITY EXCEEDANCES

The following table provides a summary of exceedances above the ANZECC (2000) guidelines for the protection of 95% of fresh water and marine species for the collected water samples.

Table 6: Summary of Quarterly Water Monitoring Exceedances

Sample ID	Exceedances		Comments
	Results	Guideline	
BH-1c	Ammonia 131 mg/L EC 6,740 µS/cm	0.91 mg/L 125-2200 µS/cm	Exceedances of Ammonia, Nitrate, pH and Salinity (EC) were encountered in multiple wells at the Site. Concentrations are elevated and within range of historical data sets.
BH-3	Ammonia 20.4 mg/L Nitrate 16.9 mg/L	0.91 mg/L 0.7 mg/L	
BH-4	Ammonia 6.11 mg/L EC 2,230 µS/cm	0.91 mg/L 125-2200 µS/cm	
BH-9	Ammonia 48.6 mg/L EC 4,720 µS/cm	0.91 mg/L 125-2200 µS/cm	
BH-12r	Ammonia 0.92 mg/L EC 2,790 µS/cm Nitrate 1.76 mg/L	0.91 mg/L 125-2200 µS/cm 0.7 mg/L	
BH-13	Ammonia 1.13 mg/L Nitrate 0.97 mg/L	0.91 mg/L 0.7 mg/L	
BH-14	EC 2,350 µS/cm	125-2200 µS/cm	
BH-15	Ammonia 60.8 mg/L EC 9,240 µS/cm	0.91 mg/L 125-2200 µS/cm	
BH-19r	Ammonia 4.23 mg/L	0.91 mg/L	
SWP-1	No exceedances		
SWP-2	No exceedances		
SWP-4	pH 8.4	6.5-8.5 pH units	
SWP-5	Dry		
SWC-up	No exceedances		
SWC-2	Ammonia 1.68 mg/L	0.91 mg/L	A single exceedance for Ammonium in SWC-2 Rocklow Creek sample. No other exceedances recorded within Rocklow Creek.
SWC-down	No exceedances		
SWC-down 2	No exceedances		
Leachate Sump	Ammonia 611 mg/L DO 3.5% EC 12,000 µS/cm	0.91 mg/L 85-100% 125-2,200 µS/cm	Elevated levels of Ammonia and EC considered to be characteristic of untreated leachate material.
Leachate Tank LP1	Ammonia 60 mg/L EC 11,00 µS/cm	0.91 mg/L 125-2,200 µS/cm	

7.0 DUST GAUGE RESULTS

The below table provides the results of the dust depositions results. A total of four (4) dust collectors were onsite for one (1) month between 15th May and 17th June 2020, in general accordance with AS3580.10.1.

Table 7: Summary of Dust Gauge Results

Sample ID	Guideline Criteria (g/m ² /month)	Total Insoluble Matter (g/m ² /month)	Comments
DDG1	4	0.6	Satisfactory
DDG2		0.4	Satisfactory
DDG3		0.8	Satisfactory
DDG4		2.4	Satisfactory

Results for depositional dust during the June 2020 quarterly monitoring period reported levels of dust between below the adopted assessment criteria of **4 g/m²/month**. The results are therefore considered satisfactory. Dust gauge locations are provided in **Figure 2** attached. It is recommended that monitoring is continued as part of the quarterly regime.

8.0 SURFACE METHANE GAS RESULTS

The surface gas monitoring from the June 2020 quarterly monitoring period reported levels of methane between 1.5 ppm and 14.3 ppm which is below the EPA license limits of 500 ppm. The results are considered satisfactory. A table of results is provided in Appendix D.

9.0 ENVIRONMENTAL ASSESSMENT

9.1 MONITORING POINT SUMMARY

Field measurements and laboratory water quality results from the quarterly June 2020 quarterly monitoring period reported concentrations analytes generally within the range historical values. Groundwater and surface water within the Site boundary reported high levels of analytes considered to be characteristic of landfill and leachate. Offsite sample locations within Rocklow Creek generally reported satisfactory results. A single exceedance for ammonium was recorded in Rocklow Creek upstream sample SWC-2. Results are considered to be consistent with historical monitoring events.

All dust gauges were reported below the site assessment criteria which was considered satisfactory.

Results of surface methane gas monitoring recorded satisfactory results. The landfill surface cap is therefore considered intact and effective.

10.0 CONCLUSION AND RECOMMENDATIONS

Based on the findings obtained during the June 2020 quarterly monitoring program the following conclusions and recommendations are provided:

- Shallow groundwater flow is expected to mimic topography with low hydraulic gradients flowing towards the south and southeast towards Rocklow creek. The nearest sensitive receptors are likely to include; recreational users of the Minnamurra River estuary environs; down gradient stakeholders; and downgradient alluvial aquifers, swamps, Rocklow Creek, Minnamurra River and Groundwater Dependent Ecosystems near discharge zones;
- Groundwater reported exceedances of the assessment criteria for; ammonia, heavy metals, nitrate and salinity (EC) within multiple groundwater bores including; BH-1c, BH-3, BH-4, BH-9, BH-12r, BH-13, BH-14, BH-15, BH-19r. This is consistent with previous monitoring events;
- Onsite surface water samples (SWP-1, SW-2, SWP-4 and SWP-5) reported a single minor exceedance for pH above the ANZECC (2000) trigger values for 95% marine/freshwater. The remaining chemical leachate indicators were reported below the assessment criteria;
- Downgradient Rocklow Creek surface water samples (SWC-Up, SWC-2, SWC-down and SWC-down 2) were generally reported within the adopted Site Assessment Criteria. A single exceedance above the ANZECC (2000) guidelines for ammonium was reported in SWC-2. The result was the first exceedance within Rocklow creek for the 2020 monitoring period. Concentrations of key leachate indicators including ammonium and nitrate were below the ANZECC (2000) trigger values for marine waters in all other Rocklow Creek sample locations;
- The existing monitoring locations and sampling regime (specified in EPL 5984) is generally considered to provide a suitable assessment of surface water, leachate and groundwater conditions;
- Surface gas methane monitoring reported satisfactory results all within the adopted assessment criteria;
- Dust deposition gauges recorded satisfactory results below the guidelines provided in AS3580.10.1. Monitoring should continue in accordance with EPL 5984 requirements;
- No non-compliances with the EPL were reported during the June 2020 quarterly monitoring period;
- Based on this review of the quarterly June 2020 monitoring period, contaminants associated with the landfill cell, leachate dam/s and general site uses are considered to be relatively consistent with the range of historical results;
- Should any change in Site conditions or incident occur which causes a potential environmental impact, a suitable environmental professional should be engaged to further assess the Site and consider requirements for any additional monitoring; and
- This report must be read in conjunction with the attached Statement of Limitations.

11.0 LIMITATIONS

This report and the associated services performed by ENRS are in accordance with the scope of services set out in the contract between ENRS and the Client. The scope of services was defined by the requests of the Client, by the time and budgetary constraints imposed by the Client, and by the availability of access to the site.

ENRS derived the data in this report primarily from visual inspections, examination of available records, interviews with individuals with information about the site, and if requested, limited sample collection and analysis made on the dates indicated. In preparing this report, ENRS has relied upon, and presumed accurate, certain information provided by government authorities, the Client and others identified herein. The report has been prepared on the basis that while ENRS believes all the information in it is deemed reliable and accurate at the time of preparing the report, it does not warrant its accuracy or completeness and to the full extent allowed by law excludes liability in contract, tort or otherwise, for any loss or damage sustained by the Client arising from or in connection with the supply or use of the whole or any part of the information in the report through any cause whatsoever.

Limitations also apply to analytical methods used in the identification of substances (or parameters). These limitations may be due to non-homogenous material being sampled (i.e. the sample to be analysed may not be representative), low concentrations, the presence of 'masking' agents and the restrictions of the approved analytical technique. As such, non-statistically significant sampling results can only be interpreted as 'indicative' and not used for quantitative assessments.

The data, findings, observations, conclusions and recommendations in the report are based solely upon the state of the site at the time of the investigation. The passage of time, manifestation of latent conditions or impacts of future events (e.g. changes in legislation, scientific knowledge, land uses, etc) may render the report inaccurate. In those circumstances, ENRS shall not be liable for any loss or damage that may be occasioned directly or indirectly through the use of, or reliance on, the contents of the report.


This report has been prepared on behalf of and for the exclusive use of the Client, and is subject to and issued in connection with the provisions of the agreement between ENRS and the Client. ENRS accepts no liability or responsibility whatsoever and expressly disclaims any responsibility for or in respect of any use of or reliance upon this report by any third party or parties.

It is the responsibility of the Client to accept if the Client so chooses any recommendations contained within and implement them in an appropriate, suitable and timely manner.

12.0 REFERENCES

- ANZECC (1996). Guidelines for the Laboratory Analysis of Contaminated Materials.
- ANZECC (2000) Australian Water Quality Guidelines for Fresh and Marine Waters. Australian and New Zealand Environment & Conservation Council. ISBN 09578245 0 5 (set).
- ANZG (2018). Australian and New Zealand Guidelines for Fresh and Marine Water Quality. Australian and New Zealand Governments and Australian state and territory governments, Canberra ACT, Australia.
- Australian Government (2011) National Health & Medical Research Council. National Resource Management Ministerial Council. National Water Quality Strategy. Australian Drinking Water Guidelines.
- Australian Standard AS 3580.10.1. Methods for sampling and analysis of ambient air; method 10.1- Determination of particulate matter - Deposited matter - Gravimetric method
- Environmental Earth Sciences (2018) Annual Report 2018- Environmental Monitoring at the Dunmore Recycling and Waste Depot, Dunmore, New South Wales
- NEPC (2013). National Environment Protection (Assessment of Site Contamination) Measure.
- Netherlands (1994) Environmental Quality Objectives in the Netherlands. Ministry of Housing, Spatial Planning and the Environment, Netherlands Government. ISBN 90-6092-783-4.
- NSW Department of Environment and Climate Change (2009a). Contaminated Sites: Guidelines on the Duty to Report Contamination under the Contaminated Land Management Act 1997
- NSW Department of Environment and Conservation (1997). Guidelines for the Assessment and Management of Groundwater Contamination
- NSW EPA (1995) Sampling Design Guidelines. ISBN 0-7310-3756-1.
- NSW EPA (2020) Guidelines for Consultants Reporting on Contaminated Sites.
- NSW Department of Environment and Conservation (1997). Guidelines for the Assessment and Management of Groundwater Contamination.
- NSW EPA (1996) Environmental Guidelines: Solid Waste Landfills. ISBN 0 7310 3774 X
- NSW EPA (2016) Environmental Guidelines: Solid Waste Landfills (2nd Edition). ISBN 978 1 76039 350 2
- NSW EPA (Mar. 2020) Environmental Protection Licence (EPL) 5984
- NSW EPA (Dec. 2017) Environmental Protection Licence (EPL) 12903
- NSW Government (1997). Protection of the Environment Operations Act.
- NSW Government (2005). Protection of the Environment (Waste) Regulation.
- NSW Landcom (2008). Managing Urban Stormwater: Soils and Construction, Volume 2B – Waste Landfills.

FIGURES



LEGEND

- Groundwater
- ▲ Surface water
- Decommissioned
- Dust gauge

200 Metres




Environment & Natural Resource Solutions
 108 Jerry Bailey Road, Shoalhaven Heads, NSW, 2535
 Tel: 02 4448 5490 Fax: 02 90374708
projects@enrs.com.au www.enrs.com.au

Client:	Shellharbour City Council	Drawn:	PL	Figure:	2
Project:	ENRS0033	Source:	NearMaps	Date:	4/02/2020
Location:	Dunmore Recycling & Waste Depot 44 Buckleys Rd, Dunmore, NSW	Scale:	NA	Title:	Site Plan
		Status:	Rev 1		




ENRS
 Environment & Natural Resource Solutions
 108 Jerry Bailey Road, Shoalhaven Heads, NSW, 2535
 Tel: 02 4448 5490 Fax: 02 90374708
projects@enrs.com.au www.enrs.com.au

Client:	Shellharbour City Council	Drawn:	PL	Figure:	3
Project:	ENRS0033	Source:	SixMaps	Date:	18/06/2020
Location:	Dunmore Recycling & Waste Depot 44 Buckleys Rd, Dunmore, NSW	Scale:	NA	Title:	Surface Gas Sample transects
		Status:	Rev 1		



ENRS Environment & Natural Resource Solutions 108 Jerry Bailey Road, Shoalhaven Heads, NSW, 2535 Tel: 02 4448 5490 Fax: 02 90374708 projects@enrs.com.au www.enrs.com.au	Client:	Shellharbour City Council	Drawn:	PL	Figure:	4
	Project:	ENRS0033	Source:	DPI	Date:	16/01/2020
	Location:	Dunmore Recycling & Waste Depot 44 Buckley's Rd, Dunmore, NSW	Scale:	NA	Title:	Geology
			Status:	Rev 1		



Client:	Shellharbour City Council	Drawn:	PL	Figure:	5
Project:	ENRS0033	Source:	SixMaps	Date:	16/01/2020
Location:	Dunmore Recycling & Waste Depot 44 Buckleys Rd, Dunmore, NSW	Scale:	NA	Title:	Registered Bores
		Status:	Rev 1		

TABLES

Table 8: Water Quality Results

Comparison of Quarterly Monitoring Results Against Site Assessment Criteria

Replace this page in PDF

TABLE 8: Total Concentration Results
EPL Quarterly Water Monitoring Results - June 2020: Dunmore Recycling and Waste Depot

GILs - Trigger Values for Freshwater (Protection of 95% of Species) ^A		-	-	-	-	-	1.9	-	-	-	0.9 (pH 8)	0.9 (pH 8)	-	0.7	0.7	-	-	-	-	-	-	-	-	-	85 - 110	-	6 - 50	-	-	-	6.5 - 8.0	2200	-				
GILs - Trigger Values for Marine Water (Protection of 95% of Species) ^A		-	-	-	-	-	-	-	-	-	0.91 (pH 8)	0.91 (pH 8)	-	-	-	-	-	-	-	-	-	-	-	-	90 - 110	-	0.5 - 10	-	-	-	-	-	-				
Australian Drinking Water Guidelines (2018) ^C	Health	-	-	-	-	-	0.5	-	-	1.5	-	-	3	50	3	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	6.5 - 8.0	-	-			
	Aesthetic	250	-	-	180	-	0.1	0.3	0.3	-	0.5	0.5	-	-	-	-	-	-	-	-	-	-	-	-	250	-	-	5	-	-	-	-	6.5 - 8.0	-	-		
Sample No.	Date Sampled	Chloride	Calcium	Magnesium	Sodium	Potassium	Manganese	Total Iron	Dissolved Iron	Fluoride	Ammonia as N	Ammonium as N	Nitrite as N	Nitrate as N	Nitrite + Nitrate as N	Total Organic Carbon	Biochemical Oxygen Demand	Hydroxide Alkalinity as CaCO3	Carbonate Alkalinity as CaCO3	Bicarbonate Alkalinity as CaCO3	Total Alkalinity as CaCO3	Sulfate as SO4 - Turbidimetric	Dissolved Oxygen	Dissolved Oxygen - % Saturation	Suspended Solids (SS)	Turbidity	Total Anions	Total Cations	Ionic Balance	pH	Electrical Conductivity	Temperature	Depth to Water (mg/l TOC)	Comments			
		Units	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	mg/L	%	mg/L	NTU	meq/L	meq/L	meq/L	meq/L	meq/L	μS/cm	°C	mg/l			
		Laboratory PQL	1	1	1	1	0.001	0.05	0.05	0.1	0.01	0.01	0.01	0.01	0.01	1	2	1	1	1	1	1	0.01	0.1	5	0.1	0.01	0.01	0.01	0.01	0.01	1	0.1	-	-		
Groundwater Bores	BH-1c	17/06/2020	790	86	-	-	145	0.122	-	12.90	0.3	131.0	-	<0.10	<0.10	179	-	<1	<1	2650	2650	<10	-	-	-	-	-	-	-	-	-	-	6.8	6740	24.5	3.38	-
	BH-3	17/06/2020	259	148	-	-	32	0.294	-	2.98	0.1	20.4	-	0.02	16.90	15	-	<1	<1	414	414	95	-	-	-	-	-	-	-	-	-	7.5	1780	18.6	3.15	-	
	BH-4	17/06/2020	293	221	-	-	20	0.244	-	5.84	<0.1	6.11	-	<0.01	<0.01	21	-	<1	<1	640	640	149	-	-	-	-	-	-	-	-	-	7.2	2230	18.3	4.37	-	
	BH-9	17/06/2020	627	228	-	-	82	1.000	-	8.24	0.4	48.6	-	0.01	<0.01	0.01	81	-	<1	<1	1530	1530	<1	-	-	-	-	-	-	-	-	6.9	4720	22.2	2.35	-	
	BH-12r	17/06/2020	425	309	-	-	66	0.722	-	9.06	0.2	0.92	-	0.05	1.76	1.81	15	-	<1	<1	605	605	420	-	-	-	-	-	-	-	-	6.8	2790	20.3	4.42	-	
	BH-13	17/06/2020	146	167	-	-	30	0.192	-	0.45	0.2	1.13	-	0.02	0.97	0.99	23	-	<1	<1	588	588	159	-	-	-	-	-	-	-	-	7.2	1690	20.8	4.4	-	
	BH-14	17/06/2020	275	173	-	-	47	0.323	-	<0.05	0.4	0.42	-	0.05	61.40	61.40	37	-	<1	<1	504	504	122	-	-	-	-	-	-	-	-	6.6	2350	18.1	4.89	-	
	BH-15	17/06/2020	2970	194	-	-	632	0.609	-	19.30	0.2	60.8	-	<0.10	<0.10	148	-	<1	<1	690	690	570	-	-	-	-	-	-	-	-	-	6.8	9240	18.5	0.74	-	
	BH-19r	17/06/2020	236	162	-	-	22	0.138	-	1.73	0.1	4.23	-	0.01	0.07	0.08	18	-	<1	<1	475	475	207	-	-	-	-	-	-	-	-	7.3	1760	22.2	4.64	-	
	Surface Water	SWP-1	17/06/2020	68	30	12	38	19	-	2.13	1.31	-	-	-	-	-	-	-	-	-	133	133	<1	-	-	20	3	5	5	1	7	-	-	-	-		
SWP-2		17/06/2020	351	87	45	267	24	-	0.08	<0.05	-	-	-	-	-	-	-	<1	14	430	430	180	-	-	7	2	22	20	5	7.9	-	-	-	-	-		
SWP-4		17/06/2020	441	58	64	365	18	-	0.17	<0.05	-	-	-	-	-	26	2	<1	49	402	402	260	-	-	14	5	26	25	3	8.1	-	-	-	-	-	Sand Mine Dam	
SWP-5		17/06/2020	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-		
SWC-up		17/06/2020	14100	337	998	8190	287	-	0.19	<0.10	-	-	0.34	<0.01	0.06	0.06	-	-	-	-	167	167	2130	-	-	18	2	445	462	2	7	-	-	-	-	-	
Rocklow Creek	SWC-2	17/06/2020	-	-	-	-	-	0.24	<0.10	-	-	1.68	<0.01	0.05	0.05	-	-	-	-	170	170	-	-	-	11	-	-	-	-	-	7.2	-	-	-	-		
	SWC-down	17/06/2020	14900	356	1060	8890	313	-	<0.10	<0.10	-	-	0.72	<0.01	0.03	0.03	-	-	-	-	162	162	2280	-	-	6	2	471	500	3	7.4	-	-	-	-		
	SWC-down 2	17/06/2020	14200	337	978	8180	287	-	0.13	<0.10	-	-	0.28	<0.01	0.04	0.04	-	-	-	-	169	169	2100	-	-	10	1	448	460	1	7.3	-	-	-	-		
Leachate	Leachate Sump	17/06/2020	1640	7	-	-	12	0.672	1.96	-	0.4	611	-	<0.20	<1.00	<1.00	238	-	<1	<1	3620	3620	104	0.35	3.5	-	-	-	-	-	7.7	12000	15.3	-	-		
	Leachate Tank LP1	17/06/2020	2040	230	-	-	190	0.605	0.69	-	0.2	60	-	<0.20	<0.20	<0.20	309	-	<1	<1	3010	3010	<20	7	73	-	-	-	-	7.6	11000	14.1	-	-			

^A Investigation levels apply to typical slightly-moderately disturbed systems. Trigger Levels for 95% of species. See ANZECC & ARMCANZ (2000) for guidance on applying these levels to different ecosystem conditions. Also the same as the NEPM (2013) ELs.
^B ANZG 2018 - pH Upper and Lower Limit for NSW Lowland Rivers (Table 3.3.2).
^C Investigation levels are taken from the health values of the Australian Drinking Water Guidelines (NHMRC 2018).

APPENDICES

Appendix A

EPL 5984 Sampling Point Summary (NSW EPA, 04/03/2020)

1	Overflow drain	Catch drain collecting overflows from Sediment Dams 1 & 2 and labelled SWP1 on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
2	Leachate monitoring	Leachate tank labelled LP1 on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
3	Groundwater monitoring	BH1c - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
5	Groundwater monitoring	BH3 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
6	Groundwater monitoring	BH4 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
7	Groundwater monitoring	BH15 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
10	Groundwater monitoring	BH13 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
11	Groundwater monitoring	BH14 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
16	Groundwater monitoring	BH19 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
17	Groundwater monitoring	BH12R - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).

18	Groundwater monitoring	BH9 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
19	Surface Water Monitoring	SWC_2 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
20	Surface Water Monitoring	SWC_UP - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
21	Surface Water Monitoring	SWC_DOWN - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).
22	Surface Water Monitoring	SWC_DOWN2 - as shown on the drawing titled "Shellharbour City Council - Dunmore, NSW - Site Layout - Figure no. 1" dated July 2019 (EPA Ref. no. DOC19/1027702).

Appendix B

Laboratory Chain of Custody (COC) & Certificates of Analysis (COA) – Water Samples



CHAIN OF CUSTODY

ALS Laboratory: please tick →

Sydney: 277 Woodpark Rd, Springfield NSW 2176
Ph: 02 8784 6655 E: samples.sydney@alsenviro.com

Brisbane: 52 Strand St, Stafford QLD 4053
Ph: 07 3243 7222 E: samples.brisbane@alsenviro.com

Melbourne: 2-4 Westall Rd, Springvale VIC 3171
Ph: 03 8549 9600 E: samples.melbourne@alsenviro.com

Perth: 10 Hod Way, Malaga WA 6090
Ph: 08 9209 7855 E: samples.perth@alsenviro.com

Newcastle: 5 Rosegum Rd, Warabrook NSW 2304
Ph: 02 4988 9433 E: samples.newcastle@alsenviro.com

Townsville: 14-15 Desma Ct, Bowen QLD 4819
Ph: 07 4756 0600 E: townsville.environmental@alsenviro.com

Adelaide: 2-1 Burma Rd, Prospect SA 5095
Ph: 08 8359 0890 E: adelaide@alsenviro.com

Launceston: 27 Wellington St, Launceston TAS 7250
Ph: 03 6331 2158 E: launceston@alsenviro.com

CLIENT: Shellharbour City Council		TURNAROUND REQUIREMENTS: <input type="checkbox"/> Standard TAT (List due date):		FOR LABORATORY USE ONLY (Circle) <input type="checkbox"/> Standard TAT (List due date): <input type="checkbox"/> Non Standard or urgent TAT (List due date):								
OFFICE: 41 Burrelli St WOLLONGONG NSW 2500		(Standard TAT may be longer for some tests e.g. Ultra Trace Organics)										
PROJECT: Dunmore Quarterly Ground Waters EPL		ALS QUOTE NO.: WO/030/19 TENDER		COC SEQUENCE NUMBER (Circle)								
ORDER NUMBER:				COC: <table border="1"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td></tr></table>		1	2	3	4	5	6	7
1	2	3	4	5	6	7						
PROJECT MANAGER: Joel Culton				OF: <table border="1"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td></tr></table>		1	2	3	4	5	6	7
1	2	3	4	5	6	7						
SAMPLER:		SAMPLER MOBILE:		RELINQUISHED BY:								
COC emailed to ALS? (YES / NO)		EDD FORMAT (or default):		Aneta								
Email Reports to :				DATE/TIME:								
Email Invoice to :				17/6/20								
				RECEIVED BY:								
				Arrian								
				DATE/TIME:								
				17/6/20								
				RELINQUISHED BY:								
				DATE/TIME:								

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL: CC reports to:

LAB ID	SAMPLE DETAILS MATRIX: Solid(S) Water(W)			CONTAINER INFORMATION	ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract attention) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle)							Field Tests
	SAMPLE ID	DATE / TIME	MATRIX		TYPE & PRESERVATIVE (refer to codes below)	TOTAL BOTTLES	Ammonia	NT-2A (Alka, So4, Cl, Fij) Filtered Ca, K	TOC	Dissolved Fe & Mn	NT-4 (NO2, NO3)	
BH1C		17/6/20 10:33	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH3		12:20	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH4		12:44	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH9		17/6/20 10:22	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH12R		10:48	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH13		11:08	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH14		12:30	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH15		11:00	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
BH19R		12:08	W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & SWL
TOTAL					10							

Environmental Division
Wollongong
Work Order Reference
EW2002778

Telephone: 02 42253125

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.

CERTIFICATE OF ANALYSIS

Work Order : **EW2002778**
Client : **SHELLHARBOUR CITY COUNCIL**
Contact : Joel Coulton
Address : LAMERTON HOUSE, LAMERTON CRESCENT
 SHELL HARBOUR CITY CENTRE NSW, AUSTRALIA 2529

Telephone : ----
Project : Dunmore Quarterly Groundwaters EPL
Order number : 126450
C-O-C number : ----
Sampler : Glenn Davies, Robert DaLio
Site : DUNMORE LANDFILL TENDER
Quote number : WO/030/19 TENDER GROUNDWATERS
No. of samples received : 9
No. of samples analysed : 9

Page : 1 of 6
Laboratory : Environmental Division NSW South Coast
Contact : Aneta Prosaroski
Address : 1/19 Ralph Black Dr, North Wollongong 2500
 4/13 Geary Pl, North Nowra 2541
 Australia NSW Australia
Telephone : +61 2 4225 3125
Date Samples Received : 17-Jun-2020 15:09
Date Analysis Commenced : 17-Jun-2020
Issue Date : 03-Jul-2020 09:16



Accreditation No. 825
 Accredited for compliance with
 ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ashesh Patel	Senior Chemist	Sydney Inorganics, Smithfield, NSW
Dian Dao		Sydney Inorganics, Smithfield, NSW
Glenn Davies	Environmental Services Representative	Laboratory - Wollongong, NSW
Hoa Nguyen	Senior Inorganic Chemist	Sydney Inorganics, Smithfield, NSW
Ivan Taylor	Analyst	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- **Analytical work for this work order will be conducted at ALS Sydney.**
- EK059G: LOR raised for NOx on samples 1 and 8 due to sample matrix.
- EK057G/EK058G: LOR raised for Nitrite and Nitrate on samples 1 and 8 due to sample matrix.
- ED041G: LOR raised for Sulfate on sample 1 due to sample matrix.
- pH performed by ALS Wollongong via in-house method EA005FD and EN67 PK.
- Electrical conductivity performed by ALS Wollongong via in-house method EA010FD and EN67 PK.
- Sampling and groundwater depth measurements completed by ALS Wollongong via inhouse sampling method EN/67.11 Groundwater Sampling.
- Temperature performed by ALS Wollongong via in-house method EA016 and EN67 PK.
- All field analysis performed by ALS Wollongong were completed at the time of sampling.
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	BH1C	BH3	BH4	BH9	BH12R
Client sampling date / time				17-Jun-2020 10:33	17-Jun-2020 12:20	17-Jun-2020 12:44	17-Jun-2020 10:22	17-Jun-2020 10:48	
Compound	CAS Number	LOR	Unit	EW2002778-001	EW2002778-002	EW2002778-003	EW2002778-004	EW2002778-005	
				Result	Result	Result	Result	Result	
EA005FD: Field pH									
pH	----	0.1	pH Unit	6.8	7.5	7.2	6.9	6.8	
EA010FD: Field Conductivity									
Electrical Conductivity (Non Compensated)	----	1	µS/cm	6740	1780	2230	4720	2790	
EA116: Temperature									
Temperature	----	0.1	°C	24.5	18.7	18.6	18.3	22.2	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	2650	414	640	1530	605	
Total Alkalinity as CaCO3	----	1	mg/L	2650	414	640	1530	605	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	<10	95	149	<1	420	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	790	259	293	627	425	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	86	148	221	228	309	
Potassium	7440-09-7	1	mg/L	145	32	20	82	66	
EG020F: Dissolved Metals by ICP-MS									
Manganese	7439-96-5	0.001	mg/L	0.122	0.294	0.244	1.00	0.722	
Iron	7439-89-6	0.05	mg/L	12.9	2.98	5.84	8.24	9.06	
EK040P: Fluoride by PC Titrator									
Fluoride	16984-48-8	0.1	mg/L	0.3	0.1	<0.1	0.4	0.2	
EK055G: Ammonia as N by Discrete Analyser									
Ammonia as N	7664-41-7	0.01	mg/L	131	20.4	6.11	48.6	0.92	
EK057G: Nitrite as N by Discrete Analyser									
Nitrite as N	14797-65-0	0.01	mg/L	<0.10	0.02	<0.01	0.01	0.05	
EK058G: Nitrate as N by Discrete Analyser									
Nitrate as N	14797-55-8	0.01	mg/L	<0.10	16.9	<0.01	<0.01	1.76	
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser									
Nitrite + Nitrate as N	----	0.01	mg/L	<0.10	16.9	<0.01	0.01	1.81	
EP005: Total Organic Carbon (TOC)									
Total Organic Carbon	----	1	mg/L	179	15	21	81	15	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	BH1C	BH3	BH4	BH9	BH12R
Client sampling date / time				17-Jun-2020 10:33	17-Jun-2020 12:20	17-Jun-2020 12:44	17-Jun-2020 10:22	17-Jun-2020 10:48	
Compound	CAS Number	LOR	Unit	EW2002778-001	EW2002778-002	EW2002778-003	EW2002778-004	EW2002778-005	
				Result	Result	Result	Result	Result	
QWI-EN 67.11 Sampling of Groundwaters									
Standing Water Level	----	0.01	m AHD	3.38	3.15	4.37	2.35	4.42	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)		Client sample ID			BH13	BH14	BH15	BH19R	----	
Client sampling date / time		17-Jun-2020 11:08			17-Jun-2020 12:30		17-Jun-2020 11:00		17-Jun-2020 12:08	----
Compound	CAS Number	LOR	Unit	EW2002778-006	EW2002778-007	EW2002778-008	EW2002778-009	-----	----	
				Result	Result	Result	Result	----	----	
EA005FD: Field pH										
pH	----	0.1	pH Unit	7.2	6.6	6.8	7.3	----	----	
EA010FD: Field Conductivity										
Electrical Conductivity (Non Compensated)	----	1	µS/cm	1690	2350	9240	1760	----	----	
EA116: Temperature										
Temperature	----	0.1	°C	20.3	20.8	18.1	18.5	----	----	
ED037P: Alkalinity by PC Titrator										
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	----	----	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	----	----	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	588	504	690	475	----	----	
Total Alkalinity as CaCO3	----	1	mg/L	588	504	690	475	----	----	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA										
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	159	122	570	207	----	----	
ED045G: Chloride by Discrete Analyser										
Chloride	16887-00-6	1	mg/L	146	275	2970	236	----	----	
ED093F: Dissolved Major Cations										
Calcium	7440-70-2	1	mg/L	167	173	194	162	----	----	
Potassium	7440-09-7	1	mg/L	30	47	632	22	----	----	
EG020F: Dissolved Metals by ICP-MS										
Manganese	7439-96-5	0.001	mg/L	0.192	0.323	0.609	0.138	----	----	
Iron	7439-89-6	0.05	mg/L	0.45	<0.05	19.3	1.73	----	----	
EK040P: Fluoride by PC Titrator										
Fluoride	16984-48-8	0.1	mg/L	0.2	0.4	0.2	0.1	----	----	
EK055G: Ammonia as N by Discrete Analyser										
Ammonia as N	7664-41-7	0.01	mg/L	1.13	0.42	60.8	4.23	----	----	
EK057G: Nitrite as N by Discrete Analyser										
Nitrite as N	14797-65-0	0.01	mg/L	0.02	0.05	<0.10	0.01	----	----	
EK058G: Nitrate as N by Discrete Analyser										
Nitrate as N	14797-55-8	0.01	mg/L	0.97	61.4	<0.10	0.07	----	----	
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser										
Nitrite + Nitrate as N	----	0.01	mg/L	0.99	61.4	<0.10	0.08	----	----	
EP005: Total Organic Carbon (TOC)										
Total Organic Carbon	----	1	mg/L	23	37	148	18	----	----	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	BH13	BH14	BH15	BH19R	----
Client sampling date / time					17-Jun-2020 11:08	17-Jun-2020 12:30	17-Jun-2020 11:00	17-Jun-2020 12:08	----
Compound	CAS Number	LOR	Unit	EW2002778-006	EW2002778-007	EW2002778-008	EW2002778-009	-----	-----
				Result	Result	Result	Result	-----	-----
QWI-EN 67.11 Sampling of Groundwaters									
Standing Water Level	----	0.01	m AHD	4.40	4.89	0.74	4.64	-----	-----



CHAIN OF CUSTODY

ALS Laboratory: please tick →

□ Sydney: 277 Woodpark Rd. Smithfield NSW 2176
Ph 02 8784 6555 E: samples.sydney@alsenviro.com

□ Brisbane: 32 Shand St. Stafford QLD 4053
Ph 07 3243 7222 E: samples.brisbane@alsenviro.com

□ Melbourne: 2-4 Westall Rd. Springvale VIC 3171
Ph 03 8549 6600 E: samples.melbourne@alsenviro.com

□ Perth: 10 Had Way, Melaleuca WA 6000
Ph: 08 9209 7855 E: samples.perth@alsenviro.com

□ Newcastle: 5 Rosegum Rd. Warabrook NSW 2304
Ph 02 4966 0433 E: samples.newcastle@alsenviro.com

□ Townsville: 14-15 Desma Ct, Bohle QLD 4813
Ph 07 4756 0600 E: townsville.environmental@alsenviro.com

□ Adelaide: 2-1 Burma Rd. Plympton SA 5005
Ph 08 8356 0800 E: adelaide@alsenviro.com

□ Launceston: 27 Wellington St. Launceston TAS 7250
Ph 03 6331 2158 E: launceston@alsenviro.com

CLIENT: Shellharbour City Council		TURNAROUND REQUIREMENTS : <input type="checkbox"/> Standard TAT (List due date):		FOR LABORATORY USE ONLY (Circle) Custody Seal intact? Yes No N/A Flick ice / frozen ice packs present upon receipt? Yes No N/A Random Sample Temperature on Receipt: °C Other comment:									
OFFICE: 41 Burrell St WOLLONGONG NSW 2500		(Standard TAT may be longer for some tests e.g., Ultra Trace Organics) <input type="checkbox"/> Non Standard or urgent TAT (List due date):											
PROJECT: Dunmore Quarterly Leachate		ALS QUOTE NO.: WO/030/19 TENDER											
ORDER NUMBER:		COC SEQUENCE NUMBER (Circle)											
PROJECT MANAGER: Joel Culton		COC: <table border="1"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td></tr></table>		1	2	3	4	5	6	7			
1	2	3	4	5	6	7							
SAMPLER:		SAMPLER MOBILE:		RECEIVED BY:		RELINQUISHED BY:							
COC emailed to ALS? (YES / NO)		EDD FORMAT (or default):		DATE/TIME: 17/6/20		DATE/TIME:							
Email Reports to :		Email Invoice to :		DATE/TIME: 17/6/20		DATE/TIME:							

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL: CC reports to:

ALS USE ONLY	SAMPLE DETAILS MATRIX: Solid(S) Water(W)			CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) <small>Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).</small>					Additional Information		
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE <small>(refer to codes below)</small>	TOTAL BOTTLES	Ammonia	NT-2A (Alka, So4, Cl, F) Filtered Ca, K	TOC	Total Fe & Mn	NT-4 (NO2, NO3)			Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
1	Leachate Storage Tank - LP1	17/6/20 8:40	W			✓	✓	✓	✓	✓			Field Tests - pH, EC, Temp & DO
					TOTAL								

Environmental Division
Wollongong
Work Order Reference
EW2002776



Telephone: 02 4225 9136

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP - Airfreight Unpreserved Plastic
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Add Sulphate Soils; B = Unpreserved Bag.

CERTIFICATE OF ANALYSIS

Work Order : **EW2002776**
Client : **SHELLHARBOUR CITY COUNCIL**
Contact : Joel Coulton
Address : LAMERTON HOUSE, LAMERTON CRESCENT
 SHELL HARBOUR CITY CENTRE NSW, AUSTRALIA 2529

Telephone : ----
Project : Dunmore Quarterly Leachate Tank EPL
Order number : 126450
C-O-C number : ----
Sampler : Glenn Davies, Robert DaLio
Site : DUNMORE LANDFILL TENDER
Quote number : WO/030/19 TENDER LEACHATE
No. of samples received : 1
No. of samples analysed : 1

Page : 1 of 4
Laboratory : Environmental Division NSW South Coast
Contact : Aneta Prosaroski
Address : 1/19 Ralph Black Dr, North Wollongong 2500
 4/13 Geary Pl, North Nowra 2541
 Australia NSW Australia
Telephone : +61 2 4225 3125
Date Samples Received : 17-Jun-2020 14:53
Date Analysis Commenced : 17-Jun-2020
Issue Date : 24-Jun-2020 19:21



Accreditation No. 825
 Accredited for compliance with
 ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ashesh Patel	Senior Chemist	Sydney Inorganics, Smithfield, NSW
Glenn Davies	Environmental Services Representative	Laboratory - Wollongong, NSW
Ivan Taylor	Analyst	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- **Analytical work for this work order will be conducted at ALS Sydney.**
- EK059G: LOR raised for NOx due to sample matrix.
- EK057G/EK058G: LOR raised for Nitrite and Nitrate due to sample matrix.
- ED041G: LOR raised for Sulfate due to sample matrix.
- pH performed by ALS Wollongong via in-house method EA005FD and EN67 PK.
- Electrical conductivity performed by ALS Wollongong via in-house method EA010FD and EN67 PK.
- Temperature performed by ALS Wollongong via in-house method EA016 and EN67 PK.
- Dissolved oxygen (DO) performed by ALS Wollongong via in-house method EA025FD and EN67 PK.
- Sampling completed by ALS Wollongong in accordance with in-house sampling method EN/67.10 Wastewaters
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.



Analytical Results

Sub-Matrix: WATER
 (Matrix: WATER)

Client sample ID

				Leachate Storage Tank LP1	----	----	----	----
Client sampling date / time				17-Jun-2020 08:40	----	----	----	----
Compound	CAS Number	LOR	Unit	EW2002776-001	-----	-----	-----	-----
				Result	----	----	----	----
EA005FD: Field pH								
pH	----	0.1	pH Unit	7.6	----	----	----	----
EA010FD: Field Conductivity								
Electrical Conductivity (Non Compensated)	----	1	µS/cm	11000	----	----	----	----
EA116: Temperature								
Temperature	----	0.1	°C	14.1	----	----	----	----
ED037P: Alkalinity by PC Titrator								
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	----	----	----	----
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	----	----	----	----
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	3010	----	----	----	----
Total Alkalinity as CaCO3	----	1	mg/L	3010	----	----	----	----
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA								
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	<20	----	----	----	----
ED045G: Chloride by Discrete Analyser								
Chloride	16887-00-6	1	mg/L	2040	----	----	----	----
ED093F: Dissolved Major Cations								
Calcium	7440-70-2	1	mg/L	230	----	----	----	----
Potassium	7440-09-7	1	mg/L	190	----	----	----	----
EG020T: Total Metals by ICP-MS								
Manganese	7439-96-5	0.001	mg/L	0.605	----	----	----	----
Iron	7439-89-6	0.05	mg/L	0.69	----	----	----	----
EK040P: Fluoride by PC Titrator								
Fluoride	16984-48-8	0.1	mg/L	0.2	----	----	----	----
EK055G: Ammonia as N by Discrete Analyser								
Ammonia as N	7664-41-7	0.01	mg/L	59.6	----	----	----	----
EK057G: Nitrite as N by Discrete Analyser								
Nitrite as N	14797-65-0	0.01	mg/L	<0.20	----	----	----	----
EK058G: Nitrate as N by Discrete Analyser								
Nitrate as N	14797-55-8	0.01	mg/L	<0.20	----	----	----	----
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser								
Nitrite + Nitrate as N	----	0.01	mg/L	<0.20	----	----	----	----
EP005: Total Organic Carbon (TOC)								



Analytical Results

Sub-Matrix: **WATER**
 (Matrix: **WATER**)

Client sample ID

				Leachate Storage Tank LP1	----	----	----	----
Client sampling date / time				17-Jun-2020 08:40	----	----	----	----
Compound	CAS Number	LOR	Unit	EW2002776-001	-----	-----	-----	-----
				Result	----	----	----	----
EP005: Total Organic Carbon (TOC) - Continued								
Total Organic Carbon	----	1	mg/L	309	----	----	----	----
EP025FD: Field Dissolved Oxygen								
Dissolved Oxygen	----	0.01	mg/L	7.43	----	----	----	----
Dissolved Oxygen - % Saturation	----	0.1	% saturation	73.1	----	----	----	----



CHAIN OF CUSTODY

ALS Laboratory, please tick →

Sydney 277 Woodpark Rd. Smithfield NSW 2178
Ph: 02 8784 8553 E: samples.sydney@alsenviro.com

Newcastle: 5 Rossopun Rd. Warwick NSW 2304
Ph: 02 4956 6433 E: samples.newcastle@alsenviro.com

Brisbane 32 Shand St. Stafford QLD 4053
Ph: 07 3243 7222 E: samples.brisbane@alsenviro.com

Townsville: 14-15 Deima Ct. Bohle QLD 4815
Ph: 07 4796 0500 E: samples.townsville@alsenviro.com

Melbourne: 2-1 Westall Rd. Springvale VIC 3171
Ph: 03 9540 6800 E: samples.melbourne@alsenviro.com

Adelaide: 2-1 Burma Rd. Pooraka SA 5095
Ph: 08 9350 0900 E: samples.adelaide@alsenviro.com

Perth 10 Hod Way, Malaga WA 6090
Ph: 08 9229 7855 E: samples.perth@alsenviro.com


Launceston: 27 Wallington St. Launceston TAS 7250
Ph: 03 6331 2159 E: samples.launceston@alsenviro.com

CLIENT: Shellharbour City Council		TURNAROUND REQUIREMENTS: <input type="checkbox"/> Standard TAT (List due date): (Standard TAT may be longer for some tests		FOR LABORATORY USE ONLY (Circle) Custody Seal Intact? Yes No WA Free Ice / Fridge on blocks present upon receipt? Yes No WA Random Sample Temperature on Receipt C Other comment:																											
OFFICE: 41 Burelli St WOLLONGONG NSW 2500		<input type="checkbox"/> Non Standard or urgent TAT (List due date):																													
PROJECT: Dunmore Quarterly Leachate		ALS QUOTE NO.: WO/030/19 TENDER		<table border="1"> <tr> <td colspan="8">COC SEQUENCE NUMBER (Circle)</td> </tr> <tr> <td>COC:</td> <td>1</td> <td>2</td> <td>3</td> <td>4</td> <td>5</td> <td>6</td> <td>7</td> </tr> <tr> <td>OP:</td> <td>1</td> <td>2</td> <td>3</td> <td>4</td> <td>5</td> <td>6</td> <td>7</td> </tr> </table>				COC SEQUENCE NUMBER (Circle)								COC:	1	2	3	4	5	6	7	OP:	1	2	3	4	5	6	7
COC SEQUENCE NUMBER (Circle)																															
COC:	1	2	3	4	5	6	7																								
OP:	1	2	3	4	5	6	7																								
ORDER NUMBER:																															
PROJECT MANAGER: Joel Culton																															
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY: Aneta		RECEIVED BY: Arrien		RELINQUISHED BY:		RECEIVED BY:																							
COC emailed to ALS? (YES / NO)		EDD FORMAT (or default):		DATE/TIME: 17/6/20		DATE/TIME:		DATE/TIME:																							
Email Reports to:				DATE/TIME:		DATE/TIME:		DATE/TIME:																							
Email Invoice to:				DATE/TIME:		DATE/TIME:		DATE/TIME:																							

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL: CC reports to:

ALS USE ONLY	SAMPLE DETAILS MATRIX: Solid(S) Water(W)			CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) <small>Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).</small>						Additional Information	
	LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL BOTTLES	Ammonia	NT-2A (Alka, SO ₄ , Cl, F) Filtered Ca, K	TOC	Total Fe & Mn	NT-4 (NO ₂ , NO ₃)		Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
	Leachate Sump	17/6/20 8:30		W			✓	✓	✓	✓	✓		Field Tests - pH, EC, Temp & DO
						TOTAL	10						

Environmental Division
Wollongong
Work Order Reference
EW2002773



Telephone : 02 42253124

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic
 V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;
 Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.

CERTIFICATE OF ANALYSIS

Work Order : **EW2002773**
Client : **SHELLHARBOUR CITY COUNCIL**
Contact : Joel Coulton
Address : LAMERTON HOUSE, LAMERTON CRESCENT
 SHELL HARBOUR CITY CENTRE NSW, AUSTRALIA 2529

Telephone : ----
Project : Dunmore Quarterly Leachate
Order number : 126450
C-O-C number : ----
Sampler : ----
Site : DUNMORE LANDFILL TENDER
Quote number : WO/030/19 TENDER LEACHATE
No. of samples received : 1
No. of samples analysed : 1

Page : 1 of 4
Laboratory : Environmental Division NSW South Coast
Contact : Aneta Prosaroski
Address : 1/19 Ralph Black Dr, North Wollongong 2500
 4/13 Geary Pl, North Nowra 2541
 Australia NSW Australia
Telephone : +61 2 4225 3125
Date Samples Received : 17-Jun-2020 15:10
Date Analysis Commenced : 17-Jun-2020
Issue Date : 24-Jun-2020 19:21



Accreditation No. 825
 Accredited for compliance with
 ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ankit Joshi	Inorganic Chemist	Sydney Inorganics, Smithfield, NSW
Ashesh Patel	Senior Chemist	Sydney Inorganics, Smithfield, NSW
Glenn Davies	Environmental Services Representative	Laboratory - Wollongong, NSW
Hoa Nguyen	Senior Inorganic Chemist	Sydney Inorganics, Smithfield, NSW
Ivan Taylor	Analyst	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- **Analytical work for this work order will be conducted at ALS Sydney.**
- EK057G/EK058G: LOR raised for Nitrite and Nitrate due to sample matrix.
- EK059G: LOR raised for NOx due to sample matrix.
- pH performed by ALS Wollongong via in-house method EA005FD and EN67 PK.
- Electrical conductivity performed by ALS Wollongong via in-house method EA010FD and EN67 PK.
- Temperature performed by ALS Wollongong via in-house method EA016 and EN67 PK.
- Dissolved oxygen (DO) performed by ALS Wollongong via in-house method EA025FD and EN67 PK.
- Sampling completed by ALS Wollongong in accordance with in-house sampling method EN/67.10 Wastewaters
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)		Client sample ID			Leachate Sump	----	----	----	----
Client sampling date / time		17-Jun-2020 08:38			----	----	----	----	----
Compound	CAS Number	LOR	Unit	EW2002773-001	-----	-----	-----	-----	-----
				Result	----	----	----	----	----
EA005FD: Field pH									
pH	----	0.1	pH Unit	7.7	----	----	----	----	----
EA010FD: Field Conductivity									
Electrical Conductivity (Non Compensated)	----	1	µS/cm	12000	----	----	----	----	----
EA116: Temperature									
Temperature	----	0.1	°C	15.3	----	----	----	----	----
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	----	----	----	----	----
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	----	----	----	----	----
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	3620	----	----	----	----	----
Total Alkalinity as CaCO3	----	1	mg/L	3620	----	----	----	----	----
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	104	----	----	----	----	----
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	1640	----	----	----	----	----
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	7	----	----	----	----	----
Potassium	7440-09-7	1	mg/L	12	----	----	----	----	----
EG020T: Total Metals by ICP-MS									
Manganese	7439-96-5	0.001	mg/L	0.672	----	----	----	----	----
Iron	7439-89-6	0.05	mg/L	1.96	----	----	----	----	----
EK040P: Fluoride by PC Titrator									
Fluoride	16984-48-8	0.1	mg/L	0.4	----	----	----	----	----
EK055G: Ammonia as N by Discrete Analyser									
Ammonia as N	7664-41-7	0.01	mg/L	611	----	----	----	----	----
EK057G: Nitrite as N by Discrete Analyser									
Nitrite as N	14797-65-0	0.01	mg/L	<0.20	----	----	----	----	----
EK058G: Nitrate as N by Discrete Analyser									
Nitrate as N	14797-55-8	0.01	mg/L	<1.00	----	----	----	----	----
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser									
Nitrite + Nitrate as N	----	0.01	mg/L	<1.00	----	----	----	----	----
EP005: Total Organic Carbon (TOC)									
Total Organic Carbon	----	1	mg/L	238	----	----	----	----	----



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	Leachate Sump	----	----	----	----
Client sampling date / time				17-Jun-2020 08:38	----	----	----	----	
Compound	CAS Number	LOR	Unit	EW2002773-001	-----	-----	-----	-----	
				Result	----	----	----	----	
EP025FD: Field Dissolved Oxygen									
Dissolved Oxygen	----	0.01	mg/L	0.35	----	----	----	----	
Dissolved Oxygen - % Saturation	----	0.1	% saturation	3.5	----	----	----	----	



CHAIN OF CUSTODY

ALS Laboratory: please tick →

Sydney: 277 Woodpark Rd, Smithfield NSW 2176
Ph: 02 8784 8555 E: samples.sydney@alsenviro.com

Brisbane: 32 Shank St, Stafford QLD 4053
Ph: 07 3243 7222 E: samples.brisbane@alsenviro.com

Melbourne: 2-4 Wesslall Rd, Springvale VIC 3171
Ph: 03 8549 9600 E: samples.melbourne@alsenviro.com

Perth: 10 Hod Way, Malaga WA 6090
Ph: 08 9209 7655 E: samples.perth@alsenviro.com

Newcastle: 5 Rosegem Rd, Warabrook NSW 2304
Ph: 02 4568 9433 E: samples.newcastle@alsenviro.com

Townsville: 14-15 Desma Ct, Bohle QLD 4818
Ph: 07 4796 0600 E: townsville.environmental@alsenviro.com

Adelaide: 2-1 Burma Rd, Pooraka SA 5095
Ph: 08 8359 5890 E: adelaide@alsenviro.com

CLIENT: Shellharbour City Council	TURNAROUND REQUIREMENTS: <input type="checkbox"/> Standard TAT (List due date):	FOR LABORATORY USE ONLY (Circle) Custody Seal intact? Yes No N/A Free ice / frozen ice bricks present upon receipt? Yes No N/A Random Sample Temperature on Receipt °C Other comment:							
OFFICE: 41 Burelli St WOLLONGONG NSW 2500	(Standard TAT may be longer for some tests e.g., Ultra Trace Organics) <input type="checkbox"/> Non Standard or urgent TAT (List due date):								
PROJECT: Dunmore Quarterly Surface Waters	ALS QUOTE NO.: WO/030/19 TENDER								
ORDER NUMBER:	COC SEQUENCE NUMBER (Circle)								
PROJECT MANAGER: Joel Culton	COC: <table border="1"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td></tr></table>	1	2	3	4	5	6	7	
1	2	3	4	5	6	7			
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY: Aneta							
COC emailed to ALS? (YES / NO)	EDD FORMAT (or default):	RECEIVED BY: Arrian							
Email Reports to :		DATE/TIME: 17/6/20							
Email Invoice to :		DATE/TIME: 17/6/20							

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL: CC reports to:

ALS USE ONLY	SAMPLE DETAILS MATRIX: Solid(S) Water(W)			CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).							Additional Information	
	LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL BOTTLES	TSS	NT-1, NT-2 (Ionic Balance)	TOC & BOD	Dissolved and Total Fe	Turbidity	NH4 & NO3		Alkalinity
	SWP2		17/6/20 12:59	W			✓	✓		✓	✓			Field Tests - pH
	SWP4 - Sand Mine Dam		↓ 13:15	W			✓	✓	✓	✓	✓			Field Tests - pH
	SWP5		↓ 11:14	W			✓	✓	✓	✓	✓	DRY		Field Tests - pH
TOTAL						10								

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP - Airfreight Ur V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation by Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.

Environmental Division
Wollongong
Work Order Reference
EW2002774



Telephone: 02 42253125

CERTIFICATE OF ANALYSIS

Work Order : **EW2002774**
Client : **SHELLHARBOUR CITY COUNCIL**
Contact : Joel Coulton
Address : LAMERTON HOUSE, LAMERTON CRESCENT
 SHELL HARBOUR CITY CENTRE NSW, AUSTRALIA 2529

Telephone : ----
Project : Dunmore Quarterly Surface Water
Order number : 126450
C-O-C number : ----
Sampler : Glenn Davies, Robert DaLio
Site : DUNMORE LANDFILL TENDER
Quote number : WO/030/19 TENDER SURFACE WATER
No. of samples received : 3
No. of samples analysed : 3

Page : 1 of 3
Laboratory : Environmental Division NSW South Coast
Contact : Aneta Prosaroski
Address : 1/19 Ralph Black Dr, North Wollongong 2500
 4/13 Geary Pl, North Nowra 2541
 Australia NSW Australia
Telephone : +61 2 4225 3125
Date Samples Received : 17-Jun-2020 15:00
Date Analysis Commenced : 17-Jun-2020
Issue Date : 24-Jun-2020 19:21



Accreditation No. 825
 Accredited for compliance with
 ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ankit Joshi	Inorganic Chemist	Sydney Inorganics, Smithfield, NSW
Dian Dao		Sydney Inorganics, Smithfield, NSW
Glenn Davies	Environmental Services Representative	Laboratory - Wollongong, NSW
Hoa Nguyen	Senior Inorganic Chemist	Sydney Inorganics, Smithfield, NSW
Ivan Taylor	Analyst	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- **Analytical work for this work order will be conducted at ALS Sydney.**
- pH performed by ALS Wollongong via in-house method EA005FD and EN67 PK.
- Sampling completed by ALS Wollongong in accordance with in-house sampling method EN/67.6 Rivers and Streams.
- All field analysis performed by ALS Wollongong were completed at the time of sampling.
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	SWP2	SWP4 - Sand Mine Dam	SWP5	----	----
Client sampling date / time				17-Jun-2020 12:59	17-Jun-2020 13:15	17-Jun-2020 11:14	----	----	
Compound	CAS Number	LOR	Unit	EW2002774-001	EW2002774-002	EW2002774-003	-----	-----	
				Result	Result	Result	----	----	
EA005FD: Field pH									
pH	----	0.1	pH Unit	7.9	8.1	----	----	----	
EA025: Total Suspended Solids dried at 104 ± 2°C									
Suspended Solids (SS)	----	5	mg/L	7	14	----	----	----	
EA045: Turbidity									
Turbidity	----	0.1	NTU	1.7	4.6	----	----	----	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	----	----	----	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	----	----	----	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	430	402	----	----	----	
Total Alkalinity as CaCO3	----	1	mg/L	430	402	----	----	----	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	180	260	----	----	----	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	351	441	----	----	----	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	87	58	----	----	----	
Magnesium	7439-95-4	1	mg/L	45	64	----	----	----	
Sodium	7440-23-5	1	mg/L	267	365	----	----	----	
Potassium	7440-09-7	1	mg/L	24	18	----	----	----	
EG020F: Dissolved Metals by ICP-MS									
Iron	7439-89-6	0.05	mg/L	<0.05	<0.05	----	----	----	
EG020T: Total Metals by ICP-MS									
Iron	7439-89-6	0.05	mg/L	0.08	0.17	----	----	----	
EN055: Ionic Balance									
∅ Total Anions	----	0.01	meq/L	22.2	25.9	----	----	----	
∅ Total Cations	----	0.01	meq/L	20.3	24.5	----	----	----	
∅ Ionic Balance	----	0.01	%	4.63	2.75	----	----	----	
EN67 PK: Field Tests									
Field Observations	----	0.01	--	----	----	DRY	----	----	
EP005: Total Organic Carbon (TOC)									
Total Organic Carbon	----	1	mg/L	----	26	----	----	----	
EP030: Biochemical Oxygen Demand (BOD)									
Biochemical Oxygen Demand	----	2	mg/L	----	2	----	----	----	



CHAIN OF CUSTODY

ALS Laboratory: please tick →

□ Sydney: 277 Woodpark Rd, Smithfield NSW 2176
Ph: 02 8784 8655 E: samples.sydney@alsenviro.com

□ Brisbane: 32 Stand St, Stafford QLD 4053
Ph: 07 3243 7222 E: samples.brisbane@alsenviro.com

□ Melbourne: 2-4 Westall Rd, Springvale VIC 3171
Ph: 03 8549 9600 E: samples.melbourne@alsenviro.com

□ Perth: 10 Hol Way, Malaga WA 6060
Ph: 08 9209 7655 E: samples.perth@alsenviro.com

□ Newcastle: 5 Rosegum Rd, Warabrook NSW 2304
Ph: 02 4968 9433 E: samples.newcastle@alsenviro.com

□ Townsville: 14-15 Desma Ct, Bohle QLD 4818
Ph: 07 4796 0600 E: samples.townsville@alsenviro.com

□ Adelaide: 2-1 Burma Rd, Pooraka SA 5006
Ph: 08 8359 0890 E: samples.adelaide@alsenviro.com


□ Launceston: 27 Wellington St, Launceston TAS 7250
Ph: 03 6331 2158 E: samples.launceston@alsenviro.com

CLIENT: Shellharbour City Council	TURNAROUND REQUIREMENTS: <input type="checkbox"/> Standard TAT (List due date):	FOR LABORATORY USE ONLY (Circle) Custody Seal Intact? Yes No N/A Free Ice / frozen Ice blocks present upon receipt? Yes No N/A Random Sample Temperature on Receipt: C Other comment:							
OFFICE: 41 Burrell St WOLLONGONG NSW 2500	<input type="checkbox"/> Non Standard or urgent TAT (List due date):								
PROJECT: Dunmore Quarterly Surface Waters EPL	ALS QUOTE NO.: WO/030/19 TENDER								
ORDER NUMBER:	COC SEQUENCE NUMBER (Circle)								
PROJECT MANAGER: Joel Culton	COC: <table border="1"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td></tr></table>	1	2	3	4	5	6	7	
1	2	3	4	5	6	7			
SAMPLER:	SAMPLER MOBILE:	OF: <table border="1"><tr><td>1</td><td>2</td><td>3</td><td>4</td><td>5</td><td>6</td><td>7</td></tr></table>	1	2	3	4	5	6	7
1	2	3	4	5	6	7			
COC emailed to ALS? (YES / NO)	EDD FORMAT (or default):	RELINQUISHED BY: Aneta DATE/TIME: 17/6/20							
Email Reports to :		RECEIVED BY: Arrian DATE/TIME: 17/6/20							
Email Invoice to :		RELINQUISHED BY:							
		RECEIVED BY:							
COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL:	CC reports to:								

ALS USE ONLY	SAMPLE DETAILS MATRIX: Solid(S) Water(W)				CONTAINER INFORMATION		ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).						Additional Information	
	LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE (refer to codes below)	TOTAL BOTTLES	TSS	NT-1, NT-2 (Ionic Balance)	TOC & BOD	Dissolved and Total Fe	Turbidity	NH4 & NO3		Alkalinity
	SWP1	17/6/20 13:22	W				✓	✓	✓	✓				Field Tests - pH
	SWC_2	11:30	W				✓			✓		✓		Field Tests - pH & Temp
	SWC_UP	11:24	W				✓	✓		✓	✓	✓		Field Tests - pH & Temp
	SWC_DOWN	11:48	W				✓	✓		✓	✓	✓		Field Tests - pH & Temp
	SWC_DOWN_2	11:42	W				✓	✓		✓	✓	✓		Field Tests - pH & Temp
						TOTAL	10							

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP - Airfreight Unpreserved F
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = S
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.

Environmental Division
Wollongong
Work Order Reference
EW2002775



Telephone : 02 42263126

CERTIFICATE OF ANALYSIS

Work Order : **EW2002775**
Client : **SHELLHARBOUR CITY COUNCIL**
Contact : Joel Coulton
Address : LAMERTON HOUSE, LAMERTON CRESCENT
 SHELL HARBOUR CITY CENTRE NSW, AUSTRALIA 2529

Telephone : ----
Project : Dunmore Quarterly Surface Water EPL
Order number : 126450
C-O-C number : ----
Sampler : Glenn Davies, Robert DaLio
Site : DUNMORE LANDFILL TENDER
Quote number : WO/030/19 TENDER SURFACE WATER
No. of samples received : 5
No. of samples analysed : 5

Page : 1 of 4
Laboratory : Environmental Division NSW South Coast
Contact : Aneta Prosaroski
Address : 1/19 Ralph Black Dr, North Wollongong 2500
 4/13 Geary Pl, North Nowra 2541
 Australia NSW Australia
Telephone : +61 2 4225 3125
Date Samples Received : 17-Jun-2020 15:03
Date Analysis Commenced : 17-Jun-2020
Issue Date : 26-Jun-2020 16:21



Accreditation No. 825
 Accredited for compliance with
 ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ankit Joshi	Inorganic Chemist	Sydney Inorganics, Smithfield, NSW
Dian Dao		Sydney Inorganics, Smithfield, NSW
Glenn Davies	Environmental Services Representative	Laboratory - Wollongong, NSW
Ivan Taylor	Analyst	Sydney Inorganics, Smithfield, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
LOR = Limit of reporting
^ = This result is computed from individual analyte detections at or above the level of reporting
ø = ALS is not NATA accredited for these tests.
~ = Indicates an estimated value.

- **Analytical work for this work order will be conducted at ALS Sydney.**
- EG020: LOR's have been raised due to matrix interference. (High Total Dissolved Solids)
- pH performed by ALS Wollongong via in-house method EA005FD and EN67 PK.
- Sampling completed by ALS Wollongong in accordance with in-house sampling method EN/67.6 Rivers and Streams.
- All field analysis performed by ALS Wollongong were completed at the time of sampling.
- Sodium Adsorption Ratio (where reported): Where results for Na, Ca or Mg are <LOR, a concentration at half the reported LOR is incorporated into the SAR calculation. This represents a conservative approach for Na relative to the assumption that <LOR = zero concentration and a conservative approach for Ca & Mg relative to the assumption that <LOR is equivalent to the LOR concentration.



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	SWP1 Point 1	SWC_2 Point 19	SWC_UP Point 20	SWC_Down Point 21	SWC_DOWN_2 Point 22
Client sampling date / time				17-Jun-2020 13:22	17-Jun-2020 11:30	17-Jun-2020 11:24	17-Jun-2020 11:48	17-Jun-2020 11:42	
Compound	CAS Number	LOR	Unit	EW2002775-001	EW2002775-002	EW2002775-003	EW2002775-004	EW2002775-005	
				Result	Result	Result	Result	Result	
EA005FD: Field pH									
pH	----	0.1	pH Unit	7.0	7.2	7.0	7.4	7.3	
EA025: Total Suspended Solids dried at 104 ± 2°C									
Suspended Solids (SS)	----	5	mg/L	20	11	18	6	10	
EA045: Turbidity									
Turbidity	----	0.1	NTU	3.1	----	1.9	1.6	1.3	
ED037P: Alkalinity by PC Titrator									
Hydroxide Alkalinity as CaCO3	DMO-210-001	1	mg/L	<1	<1	<1	<1	<1	
Carbonate Alkalinity as CaCO3	3812-32-6	1	mg/L	<1	<1	<1	<1	<1	
Bicarbonate Alkalinity as CaCO3	71-52-3	1	mg/L	133	170	167	162	169	
Total Alkalinity as CaCO3	----	1	mg/L	133	170	167	162	169	
ED041G: Sulfate (Turbidimetric) as SO4 2- by DA									
Sulfate as SO4 - Turbidimetric	14808-79-8	1	mg/L	<1	----	2130	2280	2100	
ED045G: Chloride by Discrete Analyser									
Chloride	16887-00-6	1	mg/L	68	----	14100	14900	14200	
ED093F: Dissolved Major Cations									
Calcium	7440-70-2	1	mg/L	30	----	337	356	337	
Magnesium	7439-95-4	1	mg/L	12	----	998	1060	978	
Sodium	7440-23-5	1	mg/L	38	----	8190	8890	8180	
Potassium	7440-09-7	1	mg/L	19	----	287	313	287	
EG020F: Dissolved Metals by ICP-MS									
Iron	7439-89-6	0.05	mg/L	1.31	<0.10	<0.10	<0.10	<0.10	
EG020T: Total Metals by ICP-MS									
Iron	7439-89-6	0.05	mg/L	2.13	0.24	0.19	<0.10	0.13	
EK055G-NH4: Ammonium as N by DA									
Ammonium as N	14798-03-9_N	0.01	mg/L	----	1.68	0.34	0.72	0.28	
EK057G: Nitrite as N by Discrete Analyser									
Nitrite as N	14797-65-0	0.01	mg/L	----	<0.01	<0.01	<0.01	<0.01	
EK058G: Nitrate as N by Discrete Analyser									
Nitrate as N	14797-55-8	0.01	mg/L	----	0.05	0.06	0.03	0.04	
EK059G: Nitrite plus Nitrate as N (NOx) by Discrete Analyser									
Nitrite + Nitrate as N	----	0.01	mg/L	----	0.05	0.06	0.03	0.04	
EN055: Ionic Balance									
∅ Total Anions	----	0.01	meq/L	4.58	----	445	471	448	



Analytical Results

Sub-Matrix: WATER (Matrix: WATER)				Client sample ID	SWP1 Point 1	SWC_2 Point 19	SWC_UP Point 20	SWC_Down Point 21	SWC_DOWN_2 Point 22
Client sampling date / time					17-Jun-2020 13:22	17-Jun-2020 11:30	17-Jun-2020 11:24	17-Jun-2020 11:48	17-Jun-2020 11:42
Compound	CAS Number	LOR	Unit		EW2002775-001	EW2002775-002	EW2002775-003	EW2002775-004	EW2002775-005
					Result	Result	Result	Result	Result
EN055: Ionic Balance - Continued									
∅ Total Cations	----	0.01	meq/L		4.62	----	462	500	460
∅ Ionic Balance	----	0.01	%		0.52	----	1.88	2.96	1.41

Appendix C

Laboratory Chain of Custody (COC) & Certificates of Analysis (COA) – Dust Samples



CHAIN OF CUSTODY

ALS Laboratory: please tick →

Sydney: 277 Woodpark Rd, Smithfield NSW 2176
Ph: 02 8784 8555 E: samples.sydney@alsenviro.com
 Newcastle: 5 Rosegum Rd Warabrook NSW 2304
Ph: 02 4968 9433 E: samples.newcastle@alsenviro.com


Brisbane: 32 Shand St, Stafford QLD 4053
Ph: 07 3243 7222 E: samples.brisbane@alsenviro.com
 Townsville: 14-15 Desma Ct, Bohle QLD 4818
Ph: 07 4796 0600 E: townsville.environmental@alsenviro.com

Melbourne: 2-4 Wustall Rd, Springvale VIC 3171
Ph: 03 8549 9600 E: samples.melbourne@alsenviro.com
 Adelaide: 2-1 Burne Rd, Proraka SA 5095
Ph: 08 8359 0390 E: adelaide@alsenviro.com

Perth: 10 Hod Way, Malaga WA 6060
Ph: 08 9269 7655 E: samples.perth@alsenviro.com
 Launceston: 27 Wellington St, Launceston TAS 7250
Ph: 03 6331 2188 E: launceston@alsenviro.com

CLIENT: Shellharbour City Council	TURNAROUND REQUIREMENTS: <input type="checkbox"/> Standard TAT (List due date): (Standard TAT may be longer for some tests e.g. Ultra Trace Organics)	FOR LABORATORY USE ONLY (Circle)	
OFFICE: Dunmore	<input type="checkbox"/> Non Standard or urgent TAT (List due date):	Custody Seal intact?	Yes No N/A
PROJECT: Dunmore Dust	ALS QUOTE NO.: WO/030/19 TENDER	Free/cs / frozen ice bricks present upon receipt?	Yes No N/A
ORDER NUMBER:	COC SEQUENCE NUMBER (Circle)	Random Sample Temperature on Receipt	C
PROJECT MANAGER: Joel Culton	COC: 1 2 3 4 5 6 7	Other comment:	
SAMPLER:	SAMPLER MOBILE:	RELINQUISHED BY:	RECEIVED BY:
COC emailed to ALS? (YES / NO)	EDD FORMAT (or default):	Aneta	Arman
Email Reports to :		DATE/TIME: 17/6/20	DATE/TIME: 17/6/20
Email Invoice to :			

COMMENTS/SPECIAL HANDLING/STORAGE OR DISPOSAL: CC reports to:

ALS USE ONLY	SAMPLE DETAILS MATRIX: Solid(S) Water(W)			CONTAINER INFORMATION	ANALYSIS REQUIRED including SUITES (NB. Suite Codes must be listed to attract suite price) <small>Where Metals are required, specify Total (unfiltered bottle required) or Dissolved (field filtered bottle required).</small>				Additional Information
LAB ID	SAMPLE ID	DATE / TIME	MATRIX	TYPE & PRESERVATIVE <i>(refer to codes below)</i>	TOTAL BOTTLES	A04 (Ash, CM, TIS)			Comments on likely contaminant levels, dilutions, or samples requiring specific QC analysis etc.
	DDG1	17/6/20 9:27	AIR			✓			Environmental Division Wollongong Work Order Reference EW2002772  Telephone: 02 42253124
	DDG2	9:20	AIR			✓			
	DDG3	12:53	AIR			✓			
	DDG4	8:18	AIR			✓			
					TOTAL	10			

Water Container Codes: P = Unpreserved Plastic; N = Nitric Preserved Plastic; ORC = Nitric Preserved ORC; SH = Sodium Hydroxide/Cd Preserved; S = Sodium Hydroxide Preserved Plastic; AG = Amber Glass Unpreserved; AP = Airfreight Unpreserved Plastic
V = VOA Vial HCl Preserved; VB = VOA Vial Sodium Bisulphate Preserved; VS = VOA Vial Sulfuric Preserved; AV = Airfreight Unpreserved Vial SG = Sulfuric Preserved Amber Glass; H = HCl preserved Plastic; HS = HCl preserved Speciation bottle; SP = Sulfuric Preserved Plastic; F = Formaldehyde Preserved Glass;
Z = Zinc Acetate Preserved Bottle; E = EDTA Preserved Bottles; ST = Sterile Bottle; ASS = Plastic Bag for Acid Sulphate Soils; B = Unpreserved Bag.

CERTIFICATE OF ANALYSIS

Work Order : **EW2002772**
Client : **SHELLHARBOUR CITY COUNCIL**
Contact : Joel Coulton
Address : LAMERTON HOUSE, LAMERTON CRESCENT
 SHELL HARBOUR CITY CENTRE NSW, AUSTRALIA 2529

Telephone : ----
Project : Dunmore Landfill Dust
Order number : 126450
C-O-C number : ----
Sampler : Glenn Davies, Robert DaLio
Site : DUNMORE LANDFILL TENDER
Quote number : WO/030/19 TENDER DUST
No. of samples received : 4
No. of samples analysed : 4

Page : 1 of 2
Laboratory : Environmental Division NSW South Coast
Contact : Aneta Prosaroski
Address : 1/19 Ralph Black Dr, North Wollongong 2500
 4/13 Geary Pl, North Nowra 2541
 Australia NSW Australia
Telephone : +61 2 4225 3125
Date Samples Received : 17-Jun-2020 15:04
Date Analysis Commenced : 19-Jun-2020
Issue Date : 25-Jun-2020 11:26



Accreditation No. 825
 Accredited for compliance with
 ISO/IEC 17025 - Testing

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.

Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Joel Mullarvey	Laboratory Technician	Newcastle - Inorganics, Mayfield West, NSW



General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.
 LOR = Limit of reporting
 ^ = This result is computed from individual analyte detections at or above the level of reporting
 ø = ALS is not NATA accredited for these tests.
 ~ = Indicates an estimated value.

- Analytical work for this work order will be conducted at ALS Newcastle.
- Sample exposure period is 33 days which is outside the typical exposure period of 30 +/- 2 days as per AS3580.10.1.
- Analysis as per AS3580.10.1-2016. Samples passed through a 1mm sieve prior to analysis. NATA accreditation is not held for results reported in g/m².mth.

Analytical Results

Sub-Matrix: DEPOSITIONAL DUST
 (Matrix: AIR)

Client sample ID

				DDG1 15/05/2020 - 17/06/2020	DDG2 15/05/2020 - 17/06/2020	DDG3 15/05/2020 - 17/06/2020	DDG4 15/05/2020 - 17/06/2020	----
Client sampling date / time				17-Jun-2020 09:27	17-Jun-2020 09:20	17-Jun-2020 12:53	17-Jun-2020 08:18	----
Compound	CAS Number	LOR	Unit	EW2002772-001	EW2002772-002	EW2002772-003	EW2002772-004	-----
				Result	Result	Result	Result	----
EA120: Ash Content								
Ash Content	----	0.1	g/m ² .month	0.3	0.3	0.4	1.6	----
Ash Content (mg)	----	1	mg	6	5	8	32	----
EA125: Combustible Matter								
Combustible Matter	----	0.1	g/m ² .month	0.3	0.1	0.4	0.8	----
Combustible Matter (mg)	----	1	mg	5	3	8	15	----
EA141: Total Insoluble Matter								
Total Insoluble Matter	----	0.1	g/m ² .month	0.6	0.4	0.8	2.4	----
Total Insoluble Matter (mg)	----	1	mg	11	8	16	47	----

Appendix D

Surface Gas (Methane) Field Sheets

ALS Landfill Emissions Report

Client: Shellharbour City Council Date: 11/06/2020
 Site: Dunmore Sampler(s) Glenn Davies, Arrian Zautsen

Transact / Location	Point	GPS North	GPS East	CH4 Conc (ppm)	Comments
A	1	6168 216	302 446	4.0	
A	2	6168 230	302 447	2.8	
A	3	6168 245	302 452	2.8	
A	4	6168 262	302 455	4.6	
A	5	6168 284	302 457	4.3	
A	6	6168 300	302 456	2.1	
A	7	6168 316	302 458	2.0	
A	8	6168 333	302 460	1.6	
B	1	6168 333	302 437	1.6	
B	2	6168 318	302 437	1.4	
B	3	6168 300	302 439	2.5	
B	4	6168 282	302 440	2.8	
B	5	6168 265	302 440	2.2	
B	6	6168 244	302 440	3.6	Methane Cage
B	7	6168 224	302 437	3.2	
B	8	6168 204	302 434	2.8	
B	9	6168 176	302 434	2.3	
B	10	6168 156	302 432	2.0	
C	1	6168 415	302 383	3.2	
C	2	6168 353	302 400	2.9	
C	3	6168 292	302 414	2.5	
C	4	6168 220	302 423	2.5	
C	5	6168 196	302 424	3.3	
C	6	6168 165	302 421	4.2	
C	7	6168 132	302 417	6.8	
C	8	6168 086	302 411	7.0	
C	9	6168 054	302 408	6.1	
D	1	6168 152	302 325	3.1	
D	2	6168 173	302 315	3.1	Methane Cage
D	3	6168 195	302 314	3.5	
D	4	6168 218	302 310	3.4	
D	5	6168 231	302 307	3.7	
D	6	6168 247	302 305	3.6	
D	7	6168 262	302 304	2.7	
E	1	6168 259	302 321	1.9	
E	2	6168 239	302 330	1.8	
E	3	6168 204	302 335	2.3	
E	4	6168 170	302 338	2.7	
E	5	6168 132	302 356	2.0	
E	6	6168 113	302 360	2.5	Methane Cage
E	7	6168 079	302 366	2.5	
E	8	6168 060	302 372	2.2	
E	9	6168 258	302 389	2.1	
E	10	6168 376	302 298	1.9	
F	1	6168 062	302 382	2.4	
F	2	6168 075	302 387	2.6	
F	3	6168 129	302 391	2.2	
F	4	6168 173	302 395	2.0	
F	5	6168 216	302 387	1.9	
F	6	6168 237	302 389	2.2	
F	7	6168 276	302 386	2.1	

G	1	6168 447	302 359	1.5	
G	2	6168 427	302 324	1.7	
G	3	6168 408	302 290	2.4	
G	4	6168 406	302 260	1.5	
H	1	6168 218	302 534	2.0	
H	2	6168 183	302 582	1.9	
H	3	6168 147	302 603	1.8	
H	4	6168 115	302 622	3.1	
H	5	6168 080	302 616	4.9	
H	6	6168 085	302 579	4.0	
H	7	6168 113	302 563	3.4	
H	8	6168 168	302 528	2.4	
H	9	6168 029	302 504	2.1	
H	10	6168 954	302 498	3.5	
H	11	6168 885	302 433	1.6	
H	12	6168 873	302 376	1.7	
H	13	6168 868	302 335	2.1	
H	14	6168 869	302 284	4.2	
I	1	6168 125	302 247	4.8	
I	2	6168 124	302 206	4.1	
I	3	6168 111	302 149	2.3	
I	4	6168 110	302 096	2.0	
J	1	6168 355	302 200	1.9	
J	2	6168 302	302 218	2.0	
J	3	6168 269	302 230	4.0	
J	4	6168 201	302 254	3.8	
J	5	6168 153	302 268	14.3	
K	1	6168 524	302 384	1.8	
K	2	6168 540	302 418	1.7	
K	3	6168 548	302 448	2.7	
K	4	6168 564	302 425	2.0	
K	5	6168 557	302 401	2.7	
L	1	6168 743	302 336	2.3	
L	2	6168 700	302 305	2.2	
L	3	6168 664	302 255	2.1	
L	4	6168 623	302 237	2.1	
L	5	6168 587	302 215	2.0	
L	6	6168 549	302 178	2.1	
Compressor Shed	1			1.9	
Office	1			1.8	
Community Recycling Centre	1			2.4	
OLD Weighbridge				2.5	
OLD Weighbridge Toilet				2.5	
Revolve Shop				1.8	
Building Truckwash	1			1.9	
New Weighbridge	1			2.3	
Methane Blank (Pre testing)				1.9	Taken at entrance to Dunmore site before main gate
Methane Blank (Post testing)				2.2	Taken at entrance to Dunmore site before main gate
Comments:					
Sampling performed in accordance to EPA Environmental Guidelines Solid Waste Landfills, Second Edition, 2016 Gas concentrations are reported as raw values without correction for background concentration.					

Appendix E

Calibration Certificates

Date: 9.9.19

Attn: Meelan Liew
Air-Met Scientific Pty. Ltd.
7-11 Ceylon Street
Nunawading
Vic. 3131

O/N 721424

Calibration Verification Certificate # 5042

Manufacture/Model : Gazomat Inspectra Laser CH4 analyser
S/N : 3810912
Gases Monitored : CH4, 0-100%

		Specification +/-10%
Gas used N2 BOC High Purity reads	: 0.0ppm	
Gas used Calgaz 50ppm CH4 in Air reads	: 50.2ppm	(45-55ppm) Conforms
Gas used Calgaz 500ppm CH4 in Air reads	: 502ppm	(450-550ppm) Conforms
Gas used Calgaz 1.0% CH4 in Air reads	: 10280ppm (1.0%)	(0.9-1.1%) Conforms
Gas used Calgaz 2.5% CH4 in Air reads	: 2.6%	(2.25-2.75%) Conforms
Gas used Linde 99.9% CH4 reads	: 103.0%	(90-110%) Conforms

Comments : Calibration OK

Next Service/calibration Due : 9.9.20

Stephen Hurst
ANRI Instruments & Controls Pty Ltd